Ministry of Transportation and Transit

SPECIAL PROVISIONS APPENDIX
FOR AMENDMENTS TO THE 2025 STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION
Update #3: April 1, 2026

The following amendments apply to and take precedence over the 2025 Standard Specifications for Highway Construction, and over earlier amendments (if any).

This document is a consolidation of all SS 2025 amendments issued to date.

Amendments are presented in order of Section number, rather than release date. New amendments within this Update are flagged as ***NEW***. Others have been previously released on the indicated "Issued" date heading each provision.

Unless the context implies otherwise: *Italicized* text is instructions; unitalicized text is the amended language; Redline/Strikeout formatting or grey-shading in table cells (when used) is only presented to aid users in identifying changes that have been made within a block of text. Not all changes are marked.

SECTION 202 – GRANULAR SURFACING, BASE AND SUBBASES

NEW Issued Date: April 1, 2026

SS 202.22 Target Density (page 7 of 14) *is amended by deleting paragraph (a) and replacing it with the following:*

SS 202.22(a) Laboratory Density – Where the material gradation is within the applicable range, the Target Density shall be 100% of the Standard Proctor Maximum Dry Density obtained under the current ASTM D698, with oversize correction in accordance with ASTM D4718; or

SECTION 317 – P.E. PLASTIC DRAINAGE PIPE

Issued Date: *September 8, 2025*

SS 317.06 Requirements (page 2 of 3) *is amended by adding the following new provision:*

SS 317.06.05 Perforations – When perforated P.E. Plastic Drainage Pipe is specified, perforations shall be 8 mm to 10 mm in diameter, circular, cleanly cut, and be configured in accordance with Table 318-C and Figure 318-1 of SS 318 PVC Plastic Drainage Pipe.

For gasketed bell and spigot pipe, the pipe shall be unperforated for a length equal to the depth of the socket and/or shoulder.

SECTION 318 – PVC PLASTIC DRAINAGE PIPE

Issued Date: *September 8, 2025*

SS 318.06.04 Perforations *is amended by deleting "37.5 mm" from the first paragraph and replacing it with "375 mm".*

SECTION 412 – CONCRETE REINFORCEMENT

Issued Date: *February 3, 2025*

SS 412.11 General (page 1 of 6) *is amended by adding the following sentence to the end of the third paragraph:*

Wire ties for stainless steel reinforcing shall be double-wrapped and have a minimum diameter of 1.0 mm.

SS 412.34.01 Lapped Splices (page 5 of 6) *is amended by deleting paragraph (a) and replacing it with the following:*

(a) *Transverse bars for bridge decks shall not be spliced unless greater than standard mill lengths – 12 m for 10M bars, 18 m for larger bars, and 11.89 m for stainless steel bars – would otherwise be required.*

SECTION 757 – REVEGETATION SEEDING

Issued Date: *September 8, 2025*

SS 757.12.03 Seed Analysis Report (page 1 of 8) *is amended by deleting "*seven (7) days*" from the first sentence and replacing it with "*twenty-one (21) days*".*

ATTACHMENTS:

None