

Traffic Management Manual for Work on Roadways (TMM)

2020 Office Edition

BRITISH COLUMBIA
Ministry of Transportation and Infrastructure

Reproduction of the material in this Manual for profit, and/or alteration, is not allowed without written permission from the Ministry of Transportation and Infrastructure.

BRITISH COLUMBIA | Ministry of Transportation and Infrastructure

© 2020 Edition

FORMATTED FOR DOUBLE-SIDED PRINTING

Foreword

The 2020 Traffic Management Manual for Work on Roadways (TMM) is an update to the 2015 Interim Traffic Management Manual for Work on Roadways and accounts for edits, comments, and feedback received during the four-year phase in period.

Winter maintenance activities are not specifically covered in the TMM. BC Ministry of Transportation and Infrastructure's winter maintenance activities are defined in their Highway Maintenance Agreement and/or other written policies.

This Manual was developed through the effort and support of many individuals and organizations that provided technical expertise, drew on past experience, and applied innovation to new devices and methods of traffic control.

This page is intentionally blank.

Manual Update Record

The Traffic Management Manual for Work on Roadways will be updated when necessary to address changing circumstances and requirements (see also *Section 1.1.6: Updating the Manual*).

Users are encouraged to contribute to this process by submitting suggestions for corrections and new content to the Director of Traffic and Highway Safety Engineering, Ministry of Transportation and Infrastructure at MoTITMM@gov.bc.ca.

UPDATE RECORD		
Update Number	**Issue Date**	**Brief Description of Changes**
Rev. 1	August 2020	See Overview of Changes document on website

Acknowledgements

Many individuals, organizations, and publications contributed to the development of this Manual in 2015-2019.

BC Ministry of Transportation and Infrastructure	
Project Co-Managers	
Tracy Wynnyk, CRSP	Provincial Occupational Risk and Safety Advisor
Shawn Grant, P.Eng.	Director, Provincial Field Services
Project Team Members	
John E. Babineau, P.Eng.	District Program Engineer
Jerry Froese, P.Eng.	Manager, Traffic Engineering Policy and Standards
Hayley Fulton	Sign Design Technologist
Jennifer Hardy, P.Eng.	Senior Traffic Policy and Standards Engineer
Alicia Kosolofski	Project Management Technician
Jan Lansing	Manager, Commercial Transport
Michelle Li, P.Eng.	Traffic Policy and Standards Engineer
Kenedee Ludwar, P.Eng.	Director, Traffic and Highway Safety Engineering
Larry Macko	Sign Design Technologist
Kathy Macovichuk	Graphic Design Specialist
Ross McLean	Manager, Provincial Sign Program
Cheralee Miket	Occupational Risk and Safety Advisor Assistant
Ed Miska, P.Eng.	Executive Director, Engineering Services
Emily Reinhardt	Sign Design Technologist
Beverly van Druten-Blais	Graphic Design Specialist
Other Stakeholder Organizations	
Brenda Knight	BC Construction Safety Alliance
Sarina Hanschke	BC Construction Safety Alliance
Glen Barker	BC Road Builders – Imperial Paving
Rob Singbeil	BC Road Builders – Mainroad Contracting
Scott McMillan	BC Municipal Safety Association – City of Prince George
Joe Walls	BC Municipal Safety Association – City of Vancouver
Dale MacDonald	WorkSafeBC
Don Schouten	WorkSafeBC
Kathy Tull	WorkSafeBC

Ministry Publications	
The Traffic Management Manual for Work on Roadways was built upon a compendium of the previous Ministry Work Zone Manuals and related Ministry Technical Circulars	
Other Publications	
Geometric Design Guide for Canadian Roads, 1999	Transportation Association of Canada
Manual of Uniform Traffic Control Devices, 2009	US Federal Highway Administration
Manual on Uniform Traffic Control Devices, 2012	Minnesota Department of Transportation
Temporary Traffic Control Manual, 2011	Minnesota Department of Transportation
Temporary Workplace Traffic Control Manual, 2010	Nova Scotia Transportation and Infrastructure Renewal
Work Zone Traffic Control Guidelines, 2012	Washington State Department of Transportation
Ontario Traffic Manual – Book 7 Temporary Conditions, 2014	Ministry of Transportation Ontario

This page is intentionally blank.

Manual Table of Contents

Foreword ..... **i**

Manual Update Record ..... **iii**

Acknowledgements ..... **iv**

Manual Table of Contents **TOC-1**

INTRODUCTION

Section 1: INTRODUCTION

Contents **1-i**

1.1 Traffic Management Manual for Work on Roadways **1-1**
1.1.1 Purpose of the Manual 1-2
1.1.2 Minimum Standards in the Manual 1-2
1.1.3 Applying the Principles in the Manual 1-3
1.1.4 Organization and Content of the Manual 1-4
1.1.5 Using the Manual 1-6
1.1.6 Updating the Manual 1-6

1.2 Road Authority and Prime Contractor Responsibilities **1-7**
1.2.1 Jurisdiction 1-7
1.2.2 Work Permits 1-7
1.2.3 Traffic Control Responsibilities 1-7
1. Road Authority 1-8
2. Prime Contractor 1-8
3. Management 1-8
4. Site Supervisor/Foreman/Superintendent 1-9
5. Traffic Engineer 1-9
6. Traffic Control Manager 1-9
7. Traffic Control Supervisors and Traffic Control Persons 1-10
1.2.4 Road Work Authorization 1-10
1.2.5 Plan Submission and Review Process 1-10

PART A – TRAFFIC MANAGEMENT – SECTIONS 2 AND 3[1]

Section 2: FUNDAMENTALS OF TRAFFIC MANAGEMENT AND CONTROL

Contents **2-i**

2.1 Principles of Traffic Management **2-1**

2.1.1 Traffic Management Goals and Objectives 2-1
2.1.2 Traffic Management Principles 2-2
2.1.3 Traffic Management Process 2-2

2.2 Principles of Traffic Control **2-6**

2.2.1 Hierarchy of Controls 2-6
2.2.2 Planning and Implementing by Trained Persons 2-6
2.2.3 Minimum Disruption to Road Users 2-7
2.2.4 Clear, Positive Direction for Road Users 2-7
2.2.5 Accommodation of Other Road Users 2-8
2.2.6 Continuous Maintenance of Traffic Control Devices 2-9
2.2.7 Continuous Attention to Roadside Safety 2-9
2.2.8 Traffic Control during Inactive Work 2-10
2.2.9 Work near Railways 2-10
2.2.10 Work near Accesses and Driveways 2-10

2.3 Driver Information in Work Zones **2-11**

2.3.1 Manage Driver Expectation 2-11
2.3.2 Manage Driver Workload 2-11
2.3.3 Manage Driver Sight Distances 2-12

2.4 Management of Speed **2-13**

2.4.1 Basic Guidelines 2-13
2.4.2 Construction Speed Zones 2-13
2.4.3 Temporary Speed Zones 2-14
2.4.4 Determining the Need for a Speed Reduction 2-15
2.4.5 Transition Speed Zones 2-16
2.4.6 Assessing Speed Zone Effectiveness 2-18
2.4.7 “Slow Down, Move Over” Regulation and Work Zones 2-19
2.4.8 Highway Work Zones – Split Direction of Travel 2-20

2.5 Establishing Work on Roadways **2-21**

2.5.1 Road Authority Requirements for Work 2-21
2.5.2 Traffic Management Plan Development 2-21
2.5.3 Road Authority Acceptance 2-22
2.5.4 Compliance 2-22
2.5.5 Traffic Management Plan Documentation 2-22

[1] Part A is used on Ministry projects and recommended for use by other road authorities.

2.5.6 Traffic Management Plan Resubmission 2-23

2.6 Quality Management 2-24

2.6.1 Quality Control 2-24
2.6.2 Quality Assurance 2-24
2.6.3 Traffic Management Audits 2-24

Section 3: TRAFFIC MANAGEMENT PLANS

Contents 3-i

3.1 Introduction 3-1

3.2 Traffic Management Sub-Plans 3-2

3.2.1 Traffic Control Plan 3-2
3.2.2 Incident Management Plan 3-2
3.2.3 Public Information Plan 3-3
3.2.4 Implementation Plan 3-3

3.3 Project Category Determination 3-4

3.3.1 Initial Project Category Assessment 3-4
Table 3.1: Initial Project Category Assessment 3-5
3.3.2 Project Risk Analysis 3-7
Table 3.2: Project Risk Analysis 3-8
3.3.3 Final Project Category Determination 3-11
Table 3.3: Final Project Category Determination 3-11

3.4 Traffic Management Plan Requirements by Category 3-12

3.4.1 Category 1 Traffic Management Plan Requirements 3-12
3.4.2 Category 2 Traffic Management Plan Requirements 3-15
3.4.3 Category 3 Traffic Management Plan Requirements 3-20

3.5 Traffic Management Plan Process Summary 3-25

3.6 Potential for Traffic Incident Litigation 3-26

3.6.1 Analysis of Work Zone Incidents and Near Misses 3-27
3.6.2 Traffic Control Records 3-27

3.7 Auditing Traffic Management Plans 3-28

3.7.1 Traffic Management Plan Documentation Audit 3-28
3.7.2 Traffic Management Plan Documentation Audit Process 3-29
3.7.3 Traffic Management Plan Field Audit 3-30

PART B – TRAFFIC CONTROL – SECTIONS 4 to 5[2]

Section 4: TEMPORARY TRAFFIC CONTROL DEVICES

Contents **4-i**

4.1 Introduction **4-1**

4.1.1 Fundamental Principles 4-1
4.1.2 Safety Standards for Traffic Control Devices 4-2
4.1.3 General Requirements for Traffic Control Devices 4-2
4.1.4 New and/or Customization of Temporary Traffic Control Devices 4-2

4.2 Traffic Signs **4-3**

4.2.1 General Guidelines for Traffic Signs 4-3
4.2.2 Standard Sign Patterns 4-3
4.2.3 Sign Material 4-3
4.2.4 Retroreflectivity Standards 4-4
4.2.5 Sign Dimensions and Letter Heights 4-5
4.2.6 Sign Supports 4-6
4.2.7 Sign Selection 4-10
4.2.8 Sign Placement and Spacing 4-10

4.3 Dynamic Message Signs (DMS) **4-11**

4.3.1 Permanently-Mounted DMS 4-11
4.3.2 Portable DMS 4-11
4.3.3 DMS Fundamentals 4-12
1. Abbreviated Messages 4-12
2. DMS Placement 4-13
3. Message Guidelines 4-14
4. Operational Guidelines 4-15
5. Message Types and Categories 4-16

4.4 Pavement Markings **4-17**

4.4.1 Removal of Pavement Markings 4-17
4.4.2 Temporary Pavement Markings 4-19
4.4.3 Temporary Overlay Markers (TOMs) 4-21

[2] Part B is mandatory for Ministry projects and recommended for municipal projects.

4.5 Channelizing Devices 4-22

4.5.1 Cones 4-24
4.5.2 Tubular Markers (Tubes) 4-25
4.5.3 Drums/Barrels 4-26
4.5.4 Surface-Mounted Delineators 4-27
4.5.5 Post-Mounted Delineators 4-27
4.5.6 Vertical Panels 4-28
4.5.7 Direction Indicator Barricade/Panel 4-29
4.5.8 Barricades 4-30
4.5.9 Temporary Roadside/Median Barriers 4-32
4.5.10 Temporary Lane Separators 4-33
4.5.11 Longitudinal Channelizing Devices 4-34
4.5.12 Other Channelizing Devices 4-34

4.6 Flashing Arrow Boards (FABs) 4-35

4.6.1 FAB Specifications 4-35
1. Types 4-35
2. Minimum Requirements 4-37
3. Visibility and Light Intensity 4-37
4. Display Mode 4-38
4.6.2 FAB Setup 4-38
4.6.3 FAB Operation 4-39
4.6.4 Arrow Sticks 4-39

4.7 Automated Flagger Assistance Devices (AFADs) 4-40

4.7.1 Operation Modes 4-40
4.7.2 Deployment Guidelines 4-41
4.7.3 Equipment Requirements 4-41
4.7.4 AFAD Placement and Operating Options 4-42

4.8 Temporary and Portable Traffic Signals 4-43

4.8.1 Portable Traffic Signals - Deployment Guidelines 4-43
4.8.2 Portable Traffic Signals - Operational Guidelines 4-45
4.8.3 Portable Traffic Signal Timing Plan 4-47
Class 2 Actuated Traffic Signal Timing Plan 4-48
Example of Actuated Portable Traffic Signal Timing Calculations 4-49
Advance Warning Sign Distances 4-50

4.9 Lighting Devices 4-51

4.9.1 Flashing Vehicle Lights 4-51
4.9.2 Yellow Warning Lights 4-51
4.9.3 Roadway Lighting 4-52
4.9.4 Overhead Lighting 4-53
4.9.5 Equipment Lighting 4-53

4.10 Fencing and Screens 4-54

4.10.1 Work Zone Fencing 4-54
4.10.2 Work Zone Screens and Barrier Screens 4-55

4.11 Other Traffic Control Devices 4-56

4.11.1 Flags on Traffic Control Devices 4-56
4.11.2 Sand Bags/Weights 4-57
4.11.3 Speed Reader Boards 4-57
1. Deployment Guidelines 4-57
2. Operational Guidelines 4-58
4.11.4 Temporary Rumble Strips 4-61
4.11.5 Shadow Vehicles 4-63
4.11.6 Buffer Vehicles 4-64
4.11.7 Vehicle-Mounted Crash Attenuators 4-64
4.11.8 Temporary Crash Attenuators on Barriers 4-65
4.11.9 Pilot Cars for Work Zones 4-66
1. Communication with Stakeholders 4-66
2. Planning and Operations 4-67
3. Pilot Car Warning Lights 4-67
4. Pilot Car Signs 4-68
5. Pilot Car Radio Communications 4-69
6. Pilot Car Traffic Control 4-69

Section 5: TRAFFIC CONTROL PERSONS (TCPs)

Contents 5-i

5.1 Roles and Responsibilities 5-1

5.1.1 Traffic Control Supervisor 5-1
5.1.2 Traffic Control Persons (TCPs) 5-2

5.2 Use of TCPs in Work Zones 5-3

5.3 Minimum Requirements for TCPs 5-4

5.3.1 Physical and Mental Requirements 5-4
5.3.2 Training and Certification 5-4

5.4 Work Zone Apparel and Equipment 5-5

5.4.1 TCP Apparel and Equipment 5-5
1. Basic Requirements 5-5
2. Day-Time and Night-Time Apparel 5-6
3. Additional Requirements for Night Operations 5-7
4. Night Lighting 5-7
5. Optional Equipment 5-7
6. Lettering and ID Patches 5-7
5.4.2 Apparel Retroreflectivity for TCPs 5-7
5.4.3 Apparel for Other Onsite Workers 5-9
5.4.4 Apparel Labelling for All Onsite Workers 5-10

5.5 TCP Communications 5-11

5.5.1 Fundamental Principles 5-11
5.5.2 TCP Radios 5-13
1. Radio-Based Tasks 5-13
2. Rules for Radio Use 5-13
3. Radio Frequencies 5-13

5.6 TCP Positioning and Signals 5-14

5.6.1 Hazard and Risk Assessment 5-14
5.6.2 Positioning Rules for TCPs 5-14
5.6.3 Positioning Rules for TCPs in Intersections 5-15
5.6.4 Temporary Stop Bars 5-16
5.6.5 TCP Signals 5-17
1. Signal for Stopping Traffic 5-17
2. Signal for Slowing Traffic 5-17
3. Stopping Sight Distances 5-18

5.7 TCP Safety 5-19

5.7.1 Ability to Make Evasive Manoeuvres 5-19
5.7.2 Management of Approaching Vehicle Speeds 5-19
1. Speed Management Delineation 5-19
2. Speed Management at Night 5-20
5.7.3 Prohibitions for TCPs While Actively Controlling Traffic 5-20

5.8 Emergency Procedures 5-21

5.8.1 Passage of Emergency Vehicles and Personnel 5-21
5.8.2 Traffic Control at Emergency Scenes 5-22

PART B – TRAFFIC CONTROL – SECTIONS 6 to 19[3]

Section 6: TRAFFIC CONTROL LAYOUTS – GENERAL INSTRUCTIONS

Contents **6-i**

Important Notes for Sections 6 to 19 ..... **6-1**

6.1 Introduction to Work Zone Components **6-2**

6.2 Work Zone Components **6-4**

6.2.1 Advance Information Zone 6-4
6.2.2 Advance Warning Area 6-4
6.2.3 Transition Area and Tapers 6-4
1. Merging Taper 6-5
2. Lane Shift Taper 6-5
3. Shoulder Taper 6-5
4. TCP, AFAD, or Signal Taper 6-5
5. Downstream Taper 6-5
6.2.4 Buffer Space 6-6
6.2.5 Work Activity Area 6-6
6.2.6 Termination Area 6-7

6.3 Overlapping Work Zones **6-8**

6.4 Queue Management **6-10**

6.4.1 Advance Warning and Queue Length 6-10
6.4.2 Preventing Premature Queue Shifting 6-12

6.5 Treatment of Drop-Offs and Travel Lane Excavations **6-14**

6.5.1 Drop-Offs 6-14
6.5.2 Travel Lane Excavations 6-16

6.6 Positioning of Temporary Traffic Control Devices **6-17**

Table A – Taper Lengths 6-18
Table B – Device Spacing Lengths 6-22

6.7 Device Installation and Removal **6-24**

6.7.1 General Guidelines 6-24
6.7.2 Installation Considerations 6-25
6.7.3 Removal Considerations 6-25
6.7.4 Two-Lane, Two-Way Roadways 6-26
6.7.5 Multilane Roadways 6-29

[3] Part B is mandatory for Ministry projects and recommended for municipal projects

6.8 Inspection and Maintenance of Traffic Control 6-33

6.8.1 Responsibility for Inspection and Maintenance 6-33
6.8.2 Elements of Inspection and Maintenance 6-33
6.8.3 Field Inspection Frequency 6-34

6.9 Work Duration 6-34

6.10 Risk Evaluation for Emergent and Brief-Duration Work 6-35

6.11 Using Sections 7 to 19 6-37

6.11.1 Information in Sections 7 to 19 6-37
6.11.2 Side-by-Side Formatting 6-37
"SHOULD" Documentation 6-38
6.11.3 General Instructions for Using the Layouts in Sections 7 to 19 6-39

Section 7: TRAFFIC CONTROL LAYOUTS – TWO-LANE, TWO-WAY ROADWAYS

Contents 7-i

Legend, Table A, and Table B 7-1

7.1 General Information 7-3

7.2 Typical Construction Speed Zone Signing 7-4
– Two-Lane, Two-Way Roadway

7.3 Emergent Work (< 5 Minutes) 7-6
– Two-Lane, Two-Way Roadway

7.4 Brief-Duration Work (<15 Minutes) 7-8
– Two-Lane, Two-Way Roadway

7.5 Work on Shoulder 7-10
– Short and Long Duration

7.6 Work in Parking Lane 7-12
– Urban Area

7.7 Roadside Work – Encroachment into Travel Lane 7-14
– Short Duration

7.8 Lane Closure with TCPs – Single Lane Alternating 7-16
– Short and Long Duration

7.8.1 Lane Closure with TCPs – Single Lane Alternating 7-18
– Speed Reduction (Construction Speed Limit ≤ 50 km/h)

7.8.2 Lane Closure with TCPs – Single Lane Alternating 7-20
– Speed Reduction (Construction Speed Limit ≥ 60 km/h)

7.9 Lane Closure with AFADs 7-22
– Short and Long Duration

7.10 Lane Closure with Temporary Signals 7-24
– Single Lane Alternating – Short and Long Duration

7.11 Work on Low-Volume Roadway – No Centreline 7-26
– Short Duration

7.12 Work on Low-Volume Roadway – No Centreline 7-28
– Long Duration

7.13 Two-Way Left-Turn Lane Closed 7-30
– Short and Long Duration

7.14 Roadside Diversion 7-32
– Long Duration

7.15 One-Lane Bridge or Roadway 7-34
– Short and Long Duration

7.16 Pilot Cars 7-36

7.17 Work near a Rail System Grade Crossing 7-38

Section 8: TRAFFIC CONTROL LAYOUTS – MULTILANE UNDIVIDED ROADWAYS

Contents 8-i

Legend, Table A, and Table B 8-1

8.1 General Information 8-3

8.2 Typical Construction Speed Zone Signing 8-4

8.3 Emergent Work (< 5 Minutes) 8-6

8.4 Brief-Duration Work (<15 Minutes) 8-8

8.5 Work on Shoulder 8-10

8.6 Right Lane Closed 8-12

8.7 Left Lane Closed 8-14

8.8 Centre Lane Closure (≤ 60 km/h) 8-16

8.9 Centre Lane Closure (≥ 70 km/h) 8-18

8.10 Centreline Crossover 8-20

8.11 Two-Way Left-Turn Lane Closed 8-22

8.12 Runaway Lane Open 8-24

8.13 Runaway Lane Closed 8-26

8.14 Passing/Climbing Lanes – Lane Shift 8-28

Section 9: TRAFFIC CONTROL LAYOUTS – MULTILANE DIVIDED ROADWAYS

Contents 9-i

Legend, Table A, and Table B 9-1

9.1 General Information 9-3

9.2 Typical Construction Speed Zone Signing 9-4

9.3 Emergent Work (<5 Minutes) 9-6

9.4 Brief-Duration Work (<15 Minutes) 9-8

9.5 Work on Shoulder 9-10

9.6 Right Lane Closed 9-12

9.7 Left Lane Closed 9-14

9.8 Centre Lane Closure (≤ 60 km/h) 9-16

9.9 Centre Lane Closure (≥ 70 km/h) 9-18

9.10.1 Double Right Lane Closure 9-20

9.10.2 Double Left Lane Closure 9-22

9.11 Median Crossover 9-24

9.12 Lane Closure at Open Exit Ramp 9-26

9.13 Lane Closure at Open Entrance Ramp – Yield Condition 9-28

9.14 Lane Closure at Open Entrance Ramp – Merge Condition 9-30

9.15 Temporary Closure of Exit Ramp 9-32

9.16 Runaway Lane Open 9-34

9.17 Runaway Lane Closed 9-36

9.18 Lane Closure with Zipper Merge Signing (Queues < 800 m) 9-38

9.19 Lane Closure with Zipper Merge Signing (Queues ≥ 800 m) 9-40

Section 10: TRAFFIC CONTROL LAYOUTS – MOBILE WORK

Contents **10-i**

Legend, Table A, and Table B **10-1**

10.1 General Information **10-2**

Table D – Minimum Distances for Mobile Work 10-2

10.2 Continuously Slow-Moving Work **10-4**
– Two-Lane, Two-Way Roadway

10.3 Intermittently-Moving Work **10-6**
– Two-Lane, Two-Way Roadway

10.4 Continuously Slow-Moving Work **10-8**
– Multilane Undivided or Divided Roadway

10.5 Intermittently-Moving Work **10-10**
– Multilane Undivided or Divided Roadway

10.6 Rolling Slowdown **10-12**

Section 11: TRAFFIC CONTROL LAYOUTS – INTERSECTIONS

Contents **11-i**

Legend, Table A, and Table B **11-1**

11.1 General Information **11-2**

11.2 Intersection Lane Closure – Two-Lane, Two-Way Roadway **11-4**
with TCPs (Near Side)

11.3 Intersection Lane Closure – Two-Lane, Two-Way Roadway **11-6**
with Detour (Near Side)

11.4 Intersection Lane Closure – Two-Lane, Two-Way Roadway **11-8**
with TCPs (Far Side)

11.5 Intersection Lane Closure – Two-Lane, Two-Way Roadway **11-10**
with Detour (Far Side)

11.6 Right Lane Closure (Near Side) – Multilane Intersection **11-12**

11.7 Left Lane Closure (Far Side) – Multilane Intersection **11-14**

11.8 Right Lane Closure (Far Side) – Multilane Intersection **11-16**

11.9 Left/Right Lane Closure within Intersection – Multilane Intersection **11-18**

11.10 Right Lane Closure with Right-Turn Lane (Near Side) **11-22**
– Channelized Right Turn Open – Multilane Intersection

11.11 Two Lanes Closed (Near Side) – Multilane Intersection 11-24

11.12 Two-Lane Closure – Multilane Intersection 11-26

11.13 Multiple Lane Closure (Far Side) with Dedicated Left-Turn Lane 11-28
– Multilane Intersection

11.14 Midblock Sidewalk Detour – Multilane Roadway 11-30

11.15 Midblock Sidewalk Closure 11-32

11.16 Sidewalk Detour – Multilane Intersection 11-34

11.17 Intersection Sidewalk and Crosswalk Closure 11-38

Section 12: TRAFFIC CONTROL LAYOUTS – ROUNDABOUTS

Contents 12-i

Legend, Table A, and Table B 12-1

12.1 General Information 12-2

12.2 Lane Closure in Roundabout – Single Lane 12-4

12.3 Work Outside Roundabout 12-6

12.4 Inner Lane Closure – Multilane Roundabout 12-8

12.5 Outer Lane Closure – Multilane Roundabout 12-10

Section 13: TRAFFIC CONTROL LAYOUTS – MILLING, PAVING, SEAL COATING

Contents 13-i

Legend, Table A, and Table B 13-1

13.1 General Information 13-2

13.2 Benkleman Beam and Falling Weight Deflectometer Testing 13-5

13.3 Advance Warning for Paving Work 13-6

13.4 Paving – Work in Progress 13-8

13.5 Paving – Work Not in Progress 13-10

13.6 Seal Coating in Progress 13-12

13.7 Installing and Removing Reflectors 13-14

Section 14: TRAFFIC CONTROL LAYOUTS – PAVEMENT MARKING

Contents **14-i**

Legend, Table A, and Table B **14-1**

14.1 General Information **14-2**

14.2 Quick-Dry Long-Line Marking **14-4**
Two-Lane, Two-Way Roadway – Short and Long Duration

14.3 Quick-Dry Long-Line Marking – Right Lane **14-8**
Multilane Roadway – Short and Long Duration

14.4 Quick-Dry Long-Line Marking – Left Lane **14-10**
Multilane Roadway (Median ≥ 1 m) – Short and Long Duration

14.5 Quick-Dry Long-Line Marking – Left Lane **14-12**
Multilane Roadway (Median < 1 m, Right Shoulder ≥ 2 m)
– Short and Long Duration

14.6 Quick-Dry Long-Line Marking – Left Lane **14-14**
Multilane Roadway (Median < 1 m, Right Shoulder < 2 m)
– Short and Long Duration

14.7 Conventional Long-Line Centreline and White Line Marking **14-16**
Two-Lane, Two-Way Roadway – Short and Long Duration

14.8 Conventional Long-Line Marking **14-18**
Multilane Roadway – Short and Long Duration

14.9 Left-Turn Arrow Marking **14-20**
– Short and Long Duration

14.10 Stop Line and Crosswalk Marking – Left Lanes **14-22**
– Multilane Roadway – Short and Long Duration

14.11 Stop Line and Crosswalk Marking – Right Lanes **14-24**
– Multilane Roadway – Short and Long Duration

Section 15: TRAFFIC CONTROL LAYOUTS – SURVEYING

Contents **15-i**

Legend, Table A, and Table B **15-1**

15.1 General Information **15-3**

15.2 Surveying on Shoulder **15-4**

15.3 Surveying on Centreline **15-6**

15.4 Surveying in Intersections **15-8**

Section 16: TRAFFIC CONTROL LAYOUTS – AVALANCHE CONTROL

Contents 16-i

Legend, Table A, and Table B 16-1

16.1 General Information 16-3

16.2 Road Closure for Avalanche Control – Gates without TCPs 16-4

16.3 Road Closure for Avalanche Control – Gates with TCPs 16-6

16.4 Road Closure for Avalanche Control – Barricades and TCPs 16-8

Section 17: TRAFFIC CONTROL LAYOUTS – UTILITY WORK

Contents 17-i

Legend, Table A, and Table B 17-1

17.1 General Information 17-3

17.2 Utility Work on Centreline – Urban Area 17-4
– Short and Long Duration

17.3 Traffic Signal Relamping/Cleaning 17-6
– Short Duration

Section 18: TRAFFIC CONTROL LAYOUTS – BICYCLE LANES

Contents 18-i

Legend, Table A, and Table B 18-1

18.1 General Information on Accommodating Cyclists 18-2

18.1.1 Roadway Surface Conditions 18-2
18.1.2 Roads with Bike Lanes or Paved Shoulders 18-3
18.1.3 Roads with Shared Lanes 18-3
18.1.4 Cyclist Detours 18-4
18.1.5 Signs and Other Provisions for Cyclists 18-4

18.2 Bicycle Lane Shift 18-6

18.3 Bicycle Lane Closed – Take the Lane (≤ 50 km/h) 18-8

18.4 Bicycle Lane Closed – Share the Road 18-10

18.5 Bicycle Lane Closed – Bicycle Detour 18-12

18.6 Bicycle Lane Closed – Dismount and Walk 18-14

Section 19: TRAFFIC CONTROL LAYOUTS – OTHER SCENARIOS

Contents 19-i

Legend, Table A, and Table B 19-1

19.1 Tow Truck Recovery Operations 19-2

19.2 Roadway Closure – No Through Road – Local Road 19-4

19.3 Roadway Closure – Two-Lane, Two-Way Roadway 19-8

19.4 Roadway Closure –Multilane Roadway 19-12

19.5 Roadway Closure – Intersection (Signalized or Unsignalized) 19-16

19.6 Roadway Closure with Detour (≤ 60 km/h) 19-20

19.7 Roadway Closure with Detour (≥ 70 km/h) 19-24

19.8 Emergency Response 19-28

APPENDICES

A. GLOSSARY

Contents ..... A-i

A.1 Terms A-1

A.2 Acronyms A-15

B. STANDARD CONSTRUCTION SIGNS

Contents ..... B-i

B.1 Sign Illustrations at a Glance B-1

B.1.1 Construction and Maintenance Signs B-1
B.1.2 Regulatory Signs B-14
B.1.3 Other Signs B-16

B.2 Sizes and Applications of Individual Signs B-17

B.2.1 Construction and Maintenance Signs B-19
B.2.2 Regulatory Signs B-89
B.2.3 Other Signs B-103

C. TEMPLATES FOR TRAFFIC MANAGEMENT PLANS

Contents ..... C-i

Templates for Traffic Management and Traffic Control Plans C-1

Template for Category 1 Traffic Management Plan C-3

Daily Sign Check Form C-7

Template for Category 2 and 3 Traffic Management Plans C-9

Daily Traffic Control Log C-27