Item	Risk	Definition	Point Value	Score
Overlapping work	Low	No overlapping work	1 point	
	Medium	Another work site within 3 km; traffic control for the projects could impact one another	2 points	
	High	Work sites adjacent or overlapping	3 points	
Emergency facility (ie. hospital, police, ambulance, and fire stations)	Low	No emergency facility near work site	1 point	
	Medium	24-hour manned emergency facility	2 points	
	High	Volunteer-staffed emergency facility; consider responder access through work zone to the facility, and emergency response from facility through the work zone	3 points	
			Total Score	
			Low Risk	< 23
			Medium Risk	23 to 28
			High Risk	> 28
			Project Risk	

3.3.3 Final Project Category Determination

The matrix in *Table 3.3: Final Project Category Determination* should be used to make the final project category determination.

It combines the initial project category assessment with the results of the risk analysis to identify a final project category based on roadway and traffic characteristics and risks.

It may be appropriate to increase the final category level for high-risk projects to reflect the complexity or hazards associated with the work.

Table 3.3: Final Project Category Determination

		Initial Project Category Assessment		
		1	2	3
Project Risk	Low	Category 1	Category 2	Category 3
	Medium	Category 1	Category 2	Category 3
	High	Category 2	Category 3	Category 3

The final project category determination should be used to identify required and recommended sub-plans and special conditions addressed in the Traffic Management Plan.

This process is a guide and may not capture all components of the project which should be considered when determining the Project Category.

3.4 Traffic Management Plan Requirements by Category

See also Appendix C: Templates for Traffic Management Plans.

3.4.1 Category 1 Traffic Management Plan Requirements

Category 1 Traffic Management Plans are typically appropriate for projects on two-lane highways or roads that have minimal impact on the travelling public.

The Prime Contractor shall provide all updates of the Traffic Management Plan to the Road Authority's project representative for review and acceptance.

Category 1 Traffic Management Plans include:

- Road Authority contact information
- Description of work activity:
  - type and hours of work
  - location and size of work zone
  - lanes affected by the works, and lane configuration in work zone
  - maximum proposed delays or closure times
- Description of site factors, hazards, and the impacts of work:
  - accesses and/or intersections that will be affected by the work zone or by traffic control devices
  - mitigation measures to be implemented for the identified site factors, hazards, and impacts of the work

Note: 1. Additional documentation may be required by the Road Authority.

2. If the Traffic Management Plan uses the Template for Category 1 Traffic Management Plan provided in *Appendix C: Templates for Traffic Management Plans*, daily updates will be required using the Daily Sign Check Form that is also provided in *Appendix C*.

Category 1 Traffic Control Plan

A Traffic Control Plan is required for Category 1 projects. It outlines the methods and procedures for managing traffic, including:

- speed limits
- device placement and maintenance
- traffic control layouts for the work zone (for reference, see layouts in Sections 7 to 19)

Category 1 **traffic control layouts** shall:

- reference typical layouts (Sections 7 to 19) selected for the site
- include a North Arrow
- be modified for site specific consideration

Category 1 Incident Management Plan

An Incident Management plan is required when:

- the Road Authority identifies hazards within the work zone that may impact the travelling public
- special work zone accommodation is required for emergency vehicles

An Incident Management Plan is recommended when:

- hazards or risks may impact the work area and require mitigation or consideration in the Traffic Management Plan
- work zones are more than 100 metres long and the travel lanes are restricted in width
- the project requires a total road closure for any duration

Category 1 Incident Management Plans includes:

- a contact list for emergency response agencies and key stakeholders
- procedures for emergency vehicles to pass through the work site
- any additional information required by the Road Authority

Category 1 Public Information Plan

A Public Information Plan is recommended when:

- the highway will be closed for more than 10 minutes
- the project is on a two-lane roadway where traffic volumes in the affected direction exceed 500 vehicles per hour

The Prime Contractor's Public Information Plan should include:

- methods for communicating to the travelling public and the Road Authority
- appropriate, site-specific work information signs, as required
- methods for providing work updates to the Road Authority
- dynamic message sign (DMS) messaging (message and phases), if used
- any additional information required by the Road Authority

Category 1 Implementation Plan

An Implementation Plan is required when an Incident Management Plan is used.

Category 1 Implementation Plans should identify:

- names of persons responsible for overseeing implementation of the Traffic Management Plan:
  - Site Supervisor
  - Traffic Control Supervisor if known (otherwise name to be recorded on Daily Traffic Control Log)
  - Traffic Control Persons if known (otherwise name to be recorded on Daily Traffic Control Log)
- any additional information that may be required by the Road Authority

3.4.2 Category 2 Traffic Management Plan Requirements

Category 2 Traffic Management Plans are typically required for projects that may be located on higher-speed or higher-volume corridors. Impacts on the travelling public may be higher because of the roadway characteristics or the type of work to be done.

For all projects on freeways, expressways, or roads where the regular posted speed limit is 70 km/h or above, there may be a requirement to have the Traffic Management Plan prepared under the direction of a Professional Engineer who is licensed in British Columbia and qualified and experienced in traffic management planning and highway safety.

The Prime Contractor shall provide all updates of the Traffic Management Plan to the Road Authority's project representative for review and acceptance.

Category 2 Traffic Management Plans include:

- Road Authority contact information
- Description of project area:
  - classification of roadway, number of lanes (undivided, expressway, etc.)
  - regular posted speed limit
  - road alignment
- Description of work activity:
  - type and hours of work
  - location and size of work zone
  - lanes affected by the works, and lane configuration in work zone
  - maximum proposed delays or closure times
- Description of site factors, hazards and impacts:
  - location, nature, and impacts of hazardous areas
  - accesses and/or intersections that will be affected by the work zone or by traffic control devices
  - deviations in traffic patterns and/or traffic behaviors
  - geometric roadway conditions (horizontal and vertical roadway geometry)
  - anticipated weather conditions
  - any other relevant risk factors

Category 2 Traffic Control Plan

A Traffic Control Plan is required for Category 2 projects.

It outlines the methods and procedures for managing traffic, and shall include:

- Customized Traffic Control Layouts
- work zone location using landmarks and Landmark Kilometre Inventory (LKI) where applicable
- accesses and/or intersections affected by the work zone or by traffic control devices
- speed limit(s) throughout the work zone
- device placement and maintenance
- mitigation measures for any identified hazards or potential risks
- site-specific, customized traffic control layouts for the work zone (for reference, see layouts in Sections 7 to 19):
  - during active work and as activity changes
  - during periods of inactivity
- detour routes, if available, considering:
  - all local roads to be used as detour routes, and the design speed and design vehicle for each road to be used as a detour route
  - traffic control changes necessitated by the detour route, such as temporary signals or signal timing changes
- provisions to maintain continuous, clear and safe passage for all road users and traffic during all phases of the work

Customized Traffic Control Layouts shall:

- be specific to the site
- include a North Arrow
- show schematically the placement of all traffic control devices in accordance with the standards in this Manual
- use standard symbol conventions for identifying traffic control devices (see layouts throughout the Manual and Legend on first pages of Sections 7 to 19)
- provide work zone/roadway dimensions and explanatory notes on the layouts
- label all signs on the layouts with one of the following:
  - sign number with description
  - sign number with graphical representation
  - sign number and legend
- show all sign spacing, taper lengths, offsets, etc.
- place layouts on project drawings if these are available

Category 2 Incident Management Plan

An Incident Management plan is required when:

- the Road Authority identifies hazards within the work area that may impact the travelling public
- special work zone accommodation is required for emergency vehicles

An Incident Management Plan is recommended when:

- hazards or risks may impact the work area and require mitigation or consideration in the Traffic Management Plan
- work zones are more than 100 metres long and the travel lanes are restricted in width
- the project requires a total road closure for any duration

Category 2 Incident Management Plans shall include:

- contact list for emergency response agencies and key stakeholders
- duties and responsibilities of Traffic Control Supervisor with respect to incident response operations
- types of incidents that could occur in the work zone
- procedures for responding to incidents that occur within the work zone
- procedures for accommodating emergency volunteers on emergency call-out who are travelling through the work zone in personal vehicles
- procedures for emergency vehicles to pass through the work zone
- procedures for informing and updating the Road Authority regarding:
  - incident occurrence
  - response measures taken
  - clearance measures required
  - estimated clearance time
  - resumption of pre-incident operations
- procedures for advising the travelling public of estimated clearance time and any available alternative routes
- procedures for recording incident details and reporting them to the Road Authority within 24 hours
- any additional information required by the Road Authority

Category 2 Public Information Plan

A Public Information Plan is required when:

- the highway will be closed for more than 10 minutes
- the project is on a two-lane roadway where traffic volumes in the affected direction exceed 500 vehicles per hour

A Public Information Plan is recommended when:

- for lane closures on a three- or four-lane roadway: traffic volumes in the affected direction will exceed 1,200 vehicles per hour at any time during the closure periods
- for lane closures on a six-lane roadway: traffic volumes in the affected direction will exceed 2,400 vehicles per hour at any time during the closure periods

The Prime Contractor's Public Information Plan shall include:

- Road Authority contact information
- contact numbers for stakeholders and major user groups
- methods for providing work updates to the Road Authority
- methods and procedures for communicating to the travelling public [e.g., internet, radio, print media, flyer, dynamic message signs (DMS), etc.]
- appropriate, site-specific work information signs, as required
- a process for notifying the travelling public of unscheduled traffic delays
- a process for notifying the travelling public of scheduled traffic delays and project duration at least one week before the work starts or when major changes are made to existing processes
- a process for ensuring that major user groups, emergency response agencies, transportation companies, and the travelling public are aware of the schedule of road closures or alternating lane closures at least two weeks before the work starts or as major changes occur
- a process for notifying road users of traffic pattern changes or road conditions as the work progresses and major changes occur
- methods that will be used to communicate with stakeholders and the public, including a list of DMS messages and phases (if used)
- any additional information required by the Road Authority

Category 2 Implementation Plan

An Implementation Plan is required for Category 2 projects.

Category 2 Implementation Plans should identify the individuals responsible for overseeing the implementation of the Traffic Management Plan in accordance with the duties outlined in *Section 1.2.3: Traffic Control Responsibilities* and *Section 5: Traffic Control Persons:*

- Site Supervisor – identify name and duties
- Traffic Control Manager – identify name and duties
- Traffic Control Supervisor – identify duties (name to be recorded on Daily Traffic Control Log)
- Traffic Control Persons – identify duties (name to be recorded on Daily Traffic Control Log)
- Traffic Engineer (if required) – identify name and duties
- any additional information required by the Road Authority

3.4.3 Category 3 Traffic Management Plan Requirements

Category 3 Traffic Management Plans are complex because they manage significant impacts to the travelling public as a result of higher volumes and speeds, project duration, active night work, mountainous terrain, and/or a requirement for lane closures and/or detours.

A Category 3 Traffic Management Plan shall be signed and sealed by a Professional Engineer who is licensed in British Columbia and qualified and experienced in traffic management planning and highway safety. The Professional Engineer is responsible for approving, and sealing the Traffic Management Plan and Traffic Control Plans, including all drawings and layouts.

The Prime Contractor shall provide all updates of the Traffic Management Plan to the Road Authority's project representative for review and acceptance.

Category 3 Traffic Management Plans include:

- Road Authority contact information
- Description of project area:
  - classification of roadway, number of lanes (undivided, expressway, etc.)
  - regular posted speed limit
  - road alignment
  - road volumes
- Description of work activity:
  - type and hours of work
  - location and size of work zone
  - lanes affected by the works, and lane configuration in work zone
  - maximum proposed delays or closure times
- Description of site factors, hazards, and impacts:
  - location, nature, and impacts of hazardous areas
  - accesses and/or intersections that will be affected by the work zone or by traffic control devices
  - deviations in traffic patterns and/or traffic behaviors
  - geometric roadway conditions (horizontal and vertical roadway geometry)
  - anticipated weather conditions
  - any other relevant risk factors

Category 3 Traffic Control Plan

A Traffic Control Plan is required for Category 3 projects.

It outlines the methods and procedures for managing traffic, and shall include:

- Customized Drawings
- hours of work
- work zone location and direction, and distance to nearest landmarks
- lanes affected by the works
- lane configuration in work zone
- accesses and/or intersections that will be affected by the work zone or by traffic control devices
- device placement and maintenance
- mitigation measures for identified hazards or potential risks
- traffic volume capacity during project
- proposed delays or closure times
- proposed traffic control including site-specific, customized traffic control layouts for the work zone (for reference, see layouts in Sections 7 to 19):
  - during active work and as activity changes
  - during periods of inactivity
- traffic signal timing changes necessitated by the detour route or project works
- detour routes, if available, considering:
  - all local roads to be used as detour routes, and the design speed and design vehicle for each road to be used as a detour route
  - traffic control changes necessitated by the detour route, such as temporary signals or signal timing changes
- provisions to maintain continuous, clear and safe passage for all road users and traffic during all phases of the work

Customized Drawings shall show:

- a North Arrow
- work zone location using landmarks and Landmark Kilometre Inventory (LKI) where applicable
- accesses and/or intersections affected by work zone or traffic control devices
- travel lanes affected
- resultant lane configuration, including widths
- location of restricted-width lanes
- speed limit(s) throughout the work zone
- location of hazardous areas created by road geometry or local location of vehicle storage areas if delays are anticipated
- any local roads to be used for detour routes, and the design speed and design vehicle for each road to be used as a detour route

- traffic signal location changes necessitated by the detour route or project works
- traffic control layouts showing the placement of all traffic control devices and Traffic Control Persons in accordance with the standards in this Manual
- use standard symbol conventions for identifying traffic control devices (see layouts throughout the Manual and Legend on first pages of Sections 7 to 19)
- dimensions and explanatory notes on the drawings including sign spacing, taper lengths, offsets, etc.
- traffic operations at all phases of the project
- signs labelled on the layouts with one of the following:
  - sign number with description
  - sign number with graphical representation
  - sign number and legend

Category 3 Incident Management Plan

An Incident Management Plan is required for Category 3 projects.

Category 3 Incident Management Plans shall identify:

- contact list for emergency response agencies and key stakeholders (may be a separate page or document)
- name of Traffic Control Supervisor, and duties and responsibilities with respect to incident response operations
- name of Traffic Control Manager, and duties and responsibilities with respect to incident management
- types of incidents that could occur in the work zone
- procedures for detecting and verifying incidents that occur in the work zone
- procedures for responding to incidents that occur within the work zone
- procedures for accommodating emergency volunteers on emergency call-out who are travelling through the work zone in personal vehicles
- procedures for emergency vehicles to pass through the work zone
- procedures for informing and updating the Road Authority regarding:
  - incident occurrence
  - response measures taken
  - clearance measures required
  - estimated clearance time
  - resumption of pre-incident operations
- procedures for advising the travelling public of estimated clearance time and any available alternative routes
- procedures for recording incident details and reporting them to the Road Authority within 24 hours
- procedures for restoring traffic flow around an incident site as quickly as possible
- procedures for clearing the incident and restoring normal project traffic operations as soon as possible
- process for reviewing incidents and proposing modifications to the project that will reduce severity and frequency of incidents
- any additional information required by the Road Authority

Category 3 Public Information Plan

A Public Information Plan is required for Category 3 projects.

The Prime Contractor's Public Information Plan should include:

- Road Authority contact information
- contact numbers for stakeholders and major user groups
- methods for providing work updates to the Road Authority
- methods and procedures for communicating to the travelling public [e.g., internet, radio, print media, flyer, dynamic message signs (DMS), etc.]
- appropriate, site-specific work information signs, as required
- a process for notifying the travelling public of scheduled traffic delays and project duration at least one week before the work starts or when major changes are made to existing processes
- a process for ensuring that major user groups, emergency response agencies, transportation companies, and the travelling public are aware of the schedule of road closures or alternating lane closures at least two weeks before the work starts or as major changes occur
- a process for notifying road users of traffic pattern changes or road conditions as the work progresses and major changes occur
- a process for notifying the travelling public of unanticipated traffic delays
- a list of DMS messages and phases to be used
- any additional information required by the Road Authority

Category 3 Implementation Plan

An Implementation Plan is required for Category 3 projects.

Category 3 Implementation Plans should identify the individuals responsible for overseeing the implementation of the Traffic Management Plan in accordance with the duties outlined in *Section 1.2.3: Traffic Control Responsibilities* and *Section 5: Traffic Control Persons:*

- Traffic Engineer – identify name and duties
- Site Supervisor – identify name and duties
- Traffic Control Manager – identify name and duties
- Traffic Control Supervisor – identify duties (name to be recorded on Daily Traffic Control Log)
- Traffic Control Persons – identify duties (name to be recorded on Daily Traffic Control Log)
- any additional information required by the Road Authority

3.5 Traffic Management Plan Process Summary

Process for Developing Traffic Management Plans for Ministry Projects

Step 1 Gather project information.

Step 2 Complete **Initial Category Assessment** using Table 3.1 in *Section 3.3.1: Initial Project Category Assessment.*

Step 3 Complete **Risk Analysis** using Table 3.2 in *Section 3.3.2: Project Risk Analysis.*

Step 4 Make **Final Category Determination** using Table 3.3 in *Section 3.3.3: Final Project Category Determination.*

This involves adjusting the initial category on the basis of the risk analysis outcome to determine the final category for the project.

Step 5 Develop the **Traffic Management Plan:**

- Include sub-plans required for the project category.
- Ensure that the Plan includes measures for mitigating all risks identified in the Road Authority's traffic management requirements and in Step 3 above.
- Consider using the appropriate template in *Appendix C: Templates for Traffic Management Plans* and the audit forms in *Appendix D: Traffic Management Plan Audit Forms* as guidance in developing the Plan.

Step 6 Submit the proposed Traffic Management Plan for review. See *Figure 2.2: Traffic Management Process Life Cycle* for the Ministry's Traffic Management Plan acceptance process.

Step 7 Begin work only after the Traffic Management Plan has been accepted and the Ministry has issued authorization for the work to proceed.

3.6 Potential for Traffic Incident Litigation

The objective of road authorities, contractors and utilities should be to avoid traffic incidents in work zones. The following will help to accomplish this objective:

- Know and comply with safe and effective principles of traffic control.
- Ensure that the proper devices are in place in the work zone; including times when the zone is unattended at night, weekends, holidays, etc.
- Follow all safety regulations.
- Document all actions taken on or related to traffic control placed in the work zone.
- Inspect the work zone with a view for detecting and correcting observed deficiencies in traffic control.
- Remove all material and equipment not needed at the site as soon as possible, including traffic control devices no longer required.
- Provide adequate warning, guidance and protection for motorists, pedestrians, cyclists and workers for and from all foreseeable conflicts and hazards that could result from the work being done.

In spite of the best efforts outlined above, traffic incidents may still occur and some of these may result in lawsuits against the Road Authority. Defense against such lawsuits relies to a considerable degree on records that have been kept of job related activities and of traffic control maintained in the work zone. Documentation of changes made, as and when seen to be needed, should be viewed as indication of an effort always to provide adequate traffic control.

The primary information captured in documentation of changes made include:

- What is the decision?
- When was it made?
- Why was it made?
- Who made it?
- Other information may be included and may vary based on the scope of the change(s).

3.6.1 Analysis of Work Zone Incidents and Near Misses

Work zones should be monitored and inspected regularly to identify and analyze evidence of traffic incidents and conflicts. The process for analyzing work zone incidents and near misses should be explained in the Incident Management Plan, together with the relevant responsibilities of onsite personnel.

Incidents and near misses should be investigated and relevant information recorded, together with details about any subsequent changes made to the traffic control layout (see also *Section 3.6.2: Traffic Control Records*). For example, skid marks or devices that have been moved, knocked over, or damaged may indicate that traffic control changes are required. The Road Authority should be notified of all traffic control changes.

It is important to establish and evaluate the communication processes for reporting incidents to the Road Authority, along with response actions taken, and the steps taken to re-establish normal operations and advise the public of travel delays or traffic pattern changes.

Work zone incident reports should be analyzed and recommendations implemented to assist with improving work zone operations. Once the changes are implemented, they should be monitored for effectiveness.

3.6.2 Traffic Control Records

Although record-keeping in the field can be time-consuming, particularly for a moving operation, it is important to record significant traffic control actions taken by field crews. Good traffic control records prove to be particularly critical in cases in which a traffic incident results in litigation.

The traffic control records should include, but not be limited to:

- photo logging
- photographs accompanied by brief descriptions of time, location, direction, and photographer's name
- maintaining up-to-date Traffic Control Plans by recording notes on construction plans or, preferably, updating the Traffic Control Plan
- daily diary entries of times, locations, and names of individuals involved in the installation, change, and removal of traffic control devices

When the traffic control inspection process reveals a condition that requires changes, the documentation should include:

- description and location of the change required, when the requirement was noted, and by whom
- instructions given to make changes
- what changes or replacements were made, and when
- if changes were deferred, why

Additional traffic control documentation may result from the auditing processes outlined in *Section 3.7: Auditing Traffic Management* and *Appendix D: Traffic Management Plan Audit Forms.*

3.7 Auditing Traffic Management Plans

Appendix D: Traffic Management Plan Audit Forms contains two forms intended for use by Ministry personnel who are auditing Traffic Management Plans:

- Traffic Management Plan Documentation Audit Form
- Traffic Management Plan Field Audit Form

These forms may also serve as a guide for traffic management planning by other Road Authorities, and for Prime Contractors if they wish to use them or are instructed to do so.

3.7.1 Traffic Management Plan Documentation Audit

The procedures for evaluating a proposed Traffic Management Plan should be appropriate to the complexity of the project:

- **Traffic Management Plans for Category 1 projects** may require only the verification of the information against the requirements in *Section 3.4.1: Category 1 Traffic Management Plan Requirements.*
- **Traffic Management Plans for Category 2 and 3 projects** require more comprehensive evaluations for completeness and suitability.

Each sub-plan should be evaluated for completeness with respect to the requirements (see *Section 3.4.2: Category 2 Traffic Management Plan Requirements* and *Section 3.4.3: Category 3 Traffic Management Plan Requirements*), and returned to the Prime Contractor for further attention if it is considered incomplete.

Once all sub-plans are complete, the Traffic Management Plan should be evaluated in its entirety to ensure that it meets the Road Authority's stated requirements.

Any items flagged as incomplete should be addressed in writing in the Comments section at the end of the Traffic Management Plan Documentation Audit Form. The completed form should be provided to, and discussed with, the Prime Contractor.

3.7.2 Traffic Management Plan Documentation Audit Process

Ministry personnel should use the Traffic Management Plan Documentation Audit Form in *Appendix D: Traffic Management Plan Audit Forms* in conjunction with the evaluation steps outlined below, using a system of check-marks (✓) and X's on the form to indicate compliance and non-compliance, respectively.

Traffic Management Plan Documentation Audit Process

Step 1	**Evaluate completeness of Traffic Management Plan.** Ensure that the sub-plans, layouts, and drawings are appropriate for the project category, and that all required information is provided.
Step 2	**Evaluate completeness of Traffic Control Plan.** Ensure that the proposed traffic control measures are appropriate for the project category, and that the proposed traffic control measures and layouts are suitable for the planned work activities, traffic volumes, route, and time of day.
Step 3	**Evaluate completeness of Incident Management Plan.** Ensure that all required information is provided.
Step 4	**Evaluate completeness of Public Information Plan.** Ensure that all required information is provided.
Step 5	**Evaluate completeness of Implementation Plan.** Ensure that all required information is provided.
Step 6	**Accept or reject Traffic Management Plan.** If information is missing or any sub-plans are incomplete and do not meet the stated requirements, return the Traffic Management Plan to the Prime Contractor for revision.
Step 7	**Document any conditions or limitations before sign-off.** Once all of the above requirements have been met, identify any Ministry conditions or limitations before accepting the Traffic Management Plan.
Step 8	**Authorize the work.**

3.7.3 Traffic Management Plan Field Audit

The field audit is a process of verifying that the work site practices and traffic control layouts for the project comply with the standards specified in this Manual and the Traffic Management Plan. This process is usually conducted on larger projects by the Ministry or a third-party.

Field audits include the following:

- Verify that the traffic control setups are consistent with those identified in the Traffic Management Plan and Traffic Control Plan.
- Verify that the use, positioning, and condition of signs and other traffic control devices are consistent with those identified in the Traffic Management Plan and Traffic Control Plan, and that they are performing effectively for traffic control purposes. If possible, field audits should be conducted during both daytime and night as visibility can differ significantly based on lighting conditions.
- Verify that the safety practices and apparel of Traffic Control Persons and other workers on the work site comply with the standards specified in this Manual for safety and retroreflectivity.

The Traffic Management Plan Field Audit Form in *Appendix D: Traffic Management Plan Audit Forms* should be used when conducting a field audit, using a system of check-marks (✓) and X's to indicate compliance and non-compliance, respectively.

Any items flagged as incomplete should be addressed in writing in the Comments section at the end of the Traffic Management Plan Field Audit Form. The completed form should be provided to, and discussed with, the Prime Contractor.

A follow-up audit may be required to confirm that the Prime Contractor has made and documented the appropriate changes.

Once all problems have been corrected, this should also be recorded, and copies of the completed form should be given to the Prime Contractor and placed on the project file.

.

PART B – TRAFFIC CONTROL

Section 4: Temporary Traffic Control Devices

Contents

4.1 Introduction 4-1

4.1.1 Fundamental Principles 4-1
4.1.2 Safety Standards for Traffic Control Devices 4-2
4.1.3 General Requirements for Traffic Control Devices 4-2
4.1.4 New and/or Customization of Temporary Traffic Control Devices 4-2

4.2 Traffic Signs 4-3

4.2.1 General Guidelines for Traffic Signs 4-3
4.2.2 Standard Sign Patterns 4-3
4.2.3 Sign Material 4-3
4.2.4 Retroreflectivity Standards 4-4
4.2.5 Sign Dimensions and Letter Heights 4-5
4.2.6 Sign Supports 4-6
4.2.7 Sign Selection 4-10
4.2.8 Sign Placement and Spacing 4-10

4.3 Dynamic Message Signs (DMS) 4-11

4.3.1 Permanently-Mounted DMS 4-11
4.3.2 Portable DMS 4-11
4.3.3 DMS Fundamentals 4-12
1. Abbreviated Messages 4-12
2. DMS Placement 4-13
3. Message Guidelines 4-14
4. Operational Guidelines 4-15
5. Message Types and Categories 4-16

4.4 Pavement Markings 4-17

4.4.1 Removal of Pavement Markings 4-17
4.4.2 Temporary Pavement Markings 4-19
4.4.3 Temporary Overlay Markers (TOMs) 4-21

4.5 Channelizing Devices 4-22

4.5.1 Cones 4-24
4.5.2 Tubular Markers (Tubes) 4-25
4.5.3 Drums/Barrels 4-26
4.5.4 Surface-Mounted Delineators 4-27
4.5.5 Post-Mounted Delineators 4-27
4.5.6 Vertical Panels 4-28
4.5.7 Direction Indicator Barricade/Panel 4-29
4.5.8 Barricades 4-30
4.5.9 Temporary Roadside/Median Barriers 4-32
4.5.10 Temporary Lane Separators 4-33
4.5.11 Longitudinal Channelizing Devices 4-34
4.5.12 Other Channelizing Devices 4-34

4.6 Flashing Arrow Boards (FABs) 4-35

4.6.1 FAB Specifications 4-35
1. Types 4-35
2. Minimum Requirements 4-37
3. Visibility and Light Intensity 4-37
4. Display Mode 4-38
4.6.2 FAB Setup 4-38
4.6.3 FAB Operation 4-39
4.6.4 Arrow Sticks 4-39

4.7 Automated Flagger Assistance Devices (AFADs) 4-40

4.7.1 Operation Modes 4-40
4.7.2 Deployment Guidelines 4-41
4.7.3 Equipment Requirements 4-41
4.7.4 AFAD Placement and Operating Options 4-42

4.8 Temporary and Portable Traffic Signals 4-43

4.8.1 Portable Traffic Signals - Deployment Guidelines 4-43
4.8.2 Portable Traffic Signals - Operational Guidelines 4-45
4.8.3 Portable Traffic Signal Timing Plan 4-47
Class 2 Actuated Traffic Signal Timing Plan 4-48
Example of Actuated Portable Traffic Signal Timing Calculations 4-49
Advance Warning Sign Distances 4-50

4.9 Lighting Devices 4-51

4.9.1 Flashing Vehicle Lights 4-51
4.9.2 Yellow Warning Lights 4-51
4.9.3 Roadway Lighting 4-52
4.9.4 Overhead Lighting 4-53
4.9.5 Equipment Lighting 4-53

4.10 Fencing and Screens 4-54

4.10.1 Work Zone Fencing 4-54
4.10.2 Work Zone Screens and Barrier Screens 4-55

4.11 Other Traffic Control Devices 4-56

4.11.1 Flags on Traffic Control Devices 4-56
4.11.2 Sand Bags/Weights 4-57
4.11.3 Speed Reader Boards 4-57
1. Deployment Guidelines 4-57
2. Operational Guidelines 4-58
4.11.4 Temporary Rumble Strips 4-61
4.11.5 Shadow Vehicles 4-63
4.11.6 Buffer Vehicles 4-64
4.11.7 Vehicle-Mounted Crash Attenuators 4-64
4.11.8 Temporary Crash Attenuators on Barriers 4-65
4.11.9 Pilot Cars for Work Zones 4-66
1. Communication with Stakeholders 4-66
2. Planning and Operations 4-67
3. Pilot Car Warning Lights 4-67
4. Pilot Car Signs 4-68
5. Pilot Car Radio Communications 4-69
6. Pilot Car Traffic Control 4-69

This page is intentionally blank.