speed limit	**Regular posted speed limit** – The posted speed limit of the highway prior to any planned work. This is the speed limit the Ministry has established through the H-223 form, as signed by the Chief Engineer. **Construction speed limit** – The speed limit (unchanged or reduced) in the work zone during construction activities.
spot obstruction	A roadway hazard that is less than a car length in size, such as debris on the road, a manhole, or a sink hole.
stakeholders	Individuals and organizations using the roadway or affected by the road project or works.
standard	In terms of the TMM, the standard written in this Manual establishes technical criteria, methods, processes and practices. Minimum standards are represented in this manual for controlling traffic through highway work zones. Implementation of standards usually uses words such as shall, required, or must. Several typical situations are illustrated to show the recommended application of standard devices for planned, scheduled work on roadways. See *Section 6.11: Using Sections 7 to 19*.
steep grade	A grade greater than or equal to 6%.
stop bar	A solid white line, normally 30 cm to 60 cm (12” to 24”) wide, extending across one or more lanes to indicate the point behind which vehicles are required to stop.
street	A public road used for the movement of vehicles within a municipal area.
tangent distance	The distance between the end of one taper and the beginning of the next for the same direction of travel.
taper	For a lane or shoulder closure, the gradual narrowing of the lane or shoulder using successive channelizing devices to safely guide drivers into the next lane.
taper length	For a lane or shoulder closure, the taper distance along a section of roadway required to achieve the full closure of the lane or shoulder.

Temporary Speed Zone	A temporarily lowered legal speed limit installed in a short-duration work zone at the discretion of the Supervisor and signed with Crew Working C-002 signage.
temporary stop bar	A solid white line, minimum 10” wide, which helps define the stop location in advance of a TCP.
temporary traffic control signal	A set of red, yellow, and green lights on the road or in an intersection used to temporarily control the flow of vehicles and/or pedestrians. It may be a portable signal. The design specifications for temporary signals shall be pre-approved by the Road Authority.
traffic	Includes pedestrians, ridden or herded animals, vehicles, cycles and other conveyances, either singly or together, while using a highway to travel. See also “road users” in this *Glossary.*
traffic control	The effective use of temporary traffic control devices to protect workers and move road users safely through a work zone. Traffic Control is implemented using a Traffic Management Plan.
Traffic Control Manager	The individual designated by the Prime Contractor to prepare, implement, and manage the Traffic Control Plan. It may be the Prime Contractor’s employee or sub-contractor, and it may be the Traffic Control Supervisor for simple projects.
Traffic Control Person	A person trained and certified in a manner acceptable to WorkSafeBC to direct traffic through a work zone while ensuring the safety of public traffic and workers as defined by Part 18 of WorkSafeBC’s Occupational Health and Safety Regulation.
Traffic Control Plan	A sub-plan within a Traffic Management Plan that documents how traffic control will be achieved (see *Section 3: Traffic Management Plans*). It includes a combination of text, layouts, and drawings (if required) that define specifically what traffic control measures and devices will be provided for the project, how they will be implemented, and on what schedule.

Traffic Control Supervisor	The individual designated by the Prime Contractor to supervise traffic control and personnel. If the Traffic Control Supervisor acts as a Traffic Control Person, they shall have TCP certification in order to assume the duties of a TCP and direct traffic. If the Traffic Control Supervisor is designated to ensure the requirements of Part 18.4 - Supervision in WorkSafeBC's Occupational Health and Safety (OHS) Regulations are met, they are required to be adequately trained in a manner acceptable to WorkSafeBC. See WorkSafeBC's Occupational Health and Safety (OHS) Guidelines.
traffic delay	See "vehicle delay" in this *Glossary*, unless otherwise specified.
Traffic Engineer	A Professional Engineer licensed by the Engineers and Geoscientists British Columbia (EGBC) and qualified and experienced in traffic management planning and highway safety.
traffic flow	The movement of road users/traffic on the highway. Typically this refers to the measurement of vehicular flow. However, depending on the location and numbers, other modes of transportation may also be measured.
traffic management	The strategies designed to safely mitigate the impact of construction, rehabilitation, maintenance, incident management and special events on roadways to maintain traffic mobility and worker safety. The documentation of strategies is completed using a Traffic Management Plan.
traffic management strategy	See "traffic management" in this *Glossary*.
Traffic Management Plan	The Prime Contractor's project-specific plan that details the strategies for protecting workers and safely and efficiently moving road users through the work zone, including any requirements of the Road Authority. It includes one or more of the following sub-plans, integrated into a single document that demonstrates an understanding of the site-specific issues and project requirements: • Traffic Control Plan • Incident Management Plan • Public Information Plan • Implementation Plan
traffic operations	The use of traffic control devices to maintain traffic flow on a highway.

traffic space	The portion of roadway on which traffic is routed through the work zone (see *Figure 6.1: Overview of the Six Work Zone Components*).
traffic volume	The number of vehicles within a certain amount of time. It is generally provided as Average Annual Daily Traffic (AADT) or Average Daily Traffic (ADT). It most often represents vehicular counts unless otherwise specified.
travel time	Time interval a vehicle and/or pedestrian and/or cyclist (ie. all road users impacted), or platoon requires to traverse the area under control, or the project limits.
two-lane, two-way roadway	A two-way roadway with one through lane in each direction.
undivided roadway	Roadway where there is no physical separation between the directions of travel that would prevent vehicles from travelling from one side of the roadway to the other.
upstream	Like the flow of a river, the location in front of a present location, against the direction of vehicular traffic. See also “downstream” in this *Glossary*.
utility	An organization that supplies a basic utility service, such as electricity, natural gas, water, or fibre optic service.
variable message sign	See “dynamic message sign” in this *Glossary*.
vehicle	In terms of the TMM, vehicle represents vehicular traffic best described as either a passenger car or commercial vehicle/truck.
vehicle delay	Time interval from the first vehicle being stopped at a traffic control point to the resumption of travel.
vehicles per day (vpd)	The expected number of vehicles per day on the highway during the period of time that work takes place. See also “traffic volume” in this *Glossary*.
work	The undertaking with the use of equipment or personnel of construction, rehabilitation, maintenance, incident management, or special events on or near a roadway that may impact road users.

work activity area	The specific area within a work zone where active work is taking place (see *Section 6.1: Introduction to Work Zone Components* and *Section 6.2.5: Work Activity Area*). It typically involves the presence of workers and equipment. Several work activity areas may exist within a given work zone, some separated even by several kilometres.
work zone	An area of roadway or right-of-way where road users are warned of potentially changing conditions through to the resumption of regular traffic flow. These changing conditions are typically associated with construction, maintenance, utility work, temporary/special events, or with a situation requiring emergency incident management on or alongside the roadway (see *Section 6.1: Introduction to Work Zone Components* and *Section 6.2: Work Zones Components*). The work zone is typically defined to extend from the first traffic control device to the last traffic control device as seen by the travelling public.

A.2 Acronyms[1]

AADT	Average Annual Daily Traffic (both directions)
AASHTO	American Association of State Highway and Transportation Officials
ADT	Average Daily Traffic (both directions)
AFAD	Automated Flagger Assistance Device
ASTM	American Society for Testing and Materials
CF	Counter-Flow Lane within Work Zone
CMB	Concrete Median Barrier
CMS	Changeable Message Sign
CRB	Concrete Roadside Barrier
DMI	Distance Measuring Instrument
DMS	Dynamic Message Sign
DMT	District Manager of Transportation
DT	Day-Time Work
DTN	Day-Time Work with Traffic Control Devices in Place at Night
FAB	Flashing Arrow Board
FHWA	Federal Highway Administration (USA)
FR	Flame Resistant
GPS	Global Positioning System
HOV	High-Occupancy Vehicle
LED	Light-Emitting Diode
LKI	Landmark Kilometre Inventory
LoC	Limits of Construction
MASH	AASHTO's Manual for Assessing Safety Hardware
MoT	Ministry of Transportation and Infrastructure
MUTCD	Manual of Uniform Traffic Control Devices (USA)
NCHRP	National Cooperative Highway Research Program (USA)

[1] This Manual generally avoids using acronyms to ensure clarity for non-Ministry users.

Appendix A.2 defines acronyms commonly found in other Ministry publications, as well as the few that are used in the Manual.

NT	Night-Time Work
PTS	Portable Traffic Signal
RPM	Raised Pavement Marker
RTE	Regional Traffic Engineer
RTMC	Regional Traffic Management Centre
SLAT	Single Lane Alternating Traffic
SSD	Stopping Sight Distance
STE	Senior Traffic Engineer
STOE	Senior Traffic Operations Engineer
TAC	Transportation Association of Canada
TCM	Traffic Control Manual for Work on Roadways
TCP	Traffic Control Person
TMCBC	Transportation Management Centre of British Columbia
TMG	Traffic Management Guidelines for Work on Roadways
TMM	Traffic Management Manual for Work on Roadways[2]
TMP	Traffic Management Plan
TOM	Temporary Overlay Marker
VMS	Variable Message Sign
WZ	Work Zone

[2] This Manual.

Appendix B: Standard Construction Signs

Contents[1]

B.1 Sign Illustrations at a Glance B-1

B.1.1 Construction and Maintenance Signs B-1
B.1.2 Regulatory Signs B-14
B.1.3 Other Signs B-16

B.2 Sizes and Applications of Individual Signs B-17

B.2.1 Construction and Maintenance Signs B-19
B.2.2 Regulatory Signs B-89
B.2.3 Other Signs B-103

[1] The signs provided in Appendix B are commonly used in construction applications. Additional signs are available in the Ministry's Catalogue of Standard Traffic Signs, accessible online at https://www2.gov.bc.ca/gov/content/transportation/transportation-infrastructure/engineering-standards-guidelines/traffic-engineering-safety/traffic-signs-markings#catalogue

This page is intentionally blank.

Appendix B: Standard Construction Signs

See also Section 4.2: Traffic Signs.

B.1 Sign Illustrations at a Glance

Appendix B.1 shows standard signs used temporarily for construction, maintenance, and utility work.

For detailed information on these signs, see *Appendix B.2: Sizes and Applications of Individual Signs*.

B.1.1 Construction and Maintenance Signs




C-001-1
C-001-1xx



C-001-2



C-002-1
C-002-1x



C-002-1 OL
C-002-1 OL-x



C-002-2
C-002-2x



C-002-2 OL
C-002-2 OL-x



C-002-3
C-002-3x



C-003
C-003-x



C-003-A
C-003-A-x



C-003-Ta
C-003-Ta-x



C-003-Tb
C-003-Tb-x



C-003-2
C-003-2-x



C-004
C-004-xx



C-005-A
C-005-Ax



C-005-B
C-005-Bx



C-005-C
C-005-Cx



C-005-D




C-005-LR1
C-005-LR1x



C-005-LR2
C-005-LR2x




C-006-A
C-006-Axx



C-006-LR
C-006-LRxx



C-006-4Tx



C-006-4X



C-007
C-007-x



C-008-1
C-008-1xx



C-008-2
C-008-2xx



C-008-OL
C-008-OLxx



C-009-1
C-009-1x



C-009-2
C-009-2x



C-010-LR
C-010-LRxx



C-011
C-011-xx



C-011-T
C-011-Txx



C-012
C-012-x



C-013-LR
C-013-LRxx



C-014
C-014-x



C-015
C-015-x



C-016
C-016-x



C-017-1
C-017-1x
C-017-1xx



C-017-2A
C-017-2Ax
C-017-2Axx



C-017-2B
C-017-2Bx
C-017-2Bxx



C-017-3L
C-017-3Lx
C-017-3Lxx



C-017-3R
C-017-3Rx
C-017-3Rxx



C-018-1A
C-018-1Axx



C-018-2A
C-018-2Axx



C-018-3A
C-018-3Axx



C-018-4A
C-018-4Ax



C-018-6A
C-018-6Ax
C-018-6Axx



C-018-7
C-018-7x
C-018-7xx



C-018-8A
C-018-8Ax



C-018-8L
C-018-8Lx
C-018-8Lxx



C-018-8R
C-018-8Rx
C-018-8Rxx



C-018-9
C-018-9x



C-019



C-019-T



C-020-1LR
C-020-1LRx



C-020-2L
C-020-2Lx



C-020-2R
C-020-2Rx



C-022
C-022-x
C-022-xx



C-024
C-024-x
C-024-xx



C-027



C-028
C-028-xx



C-029
C-029-xx



C-030-1A
C-030-1Axx



C-030-2
C-030-2xx



C-030-3A
C-030-3Axx



C-030-4A
C-030-4Axx



C-030-5AL
C-030-5ALxx



C-030-5AR
C-030-5ARxx



C-030-6A
C-030-6Axx



C-030-7A
C-030-7Axx



C-030-8
C-030-8xx



C-030-14
C-030-14x
C-030-14xx



C-030-15
C-030-15x
C-030-15xx



C-031
C-031-x



C-032
C-032-xx



C-033
C-033-x



C-034
C-034-x



C-036



C-037-1
C-037-2



C-038
C-038-xx




C-039
C-039-x



C-040D



C-041-xx



C-042-LR



C-042-SLR



C-043



C-044-xx



C-045-1A
C-045-1Axx



C-045-2A
C-045-2Axx



C-046
C-046-x



C-047-1
C-047-1x



C-047-2
C-047-2x



C-048-1-DS



C-048-2



C-049
C-049-x



C-050-1
C-050-1x



C-050-2
C-050-2x



C-051
C-051-x



C-052-L
C-052-Lxx



C-052-R
C-052-Rxx



C-053
C-053-xx



C-057
C-057-x



C-058-1A
C-058-1Ax
C-058-1Axx



C-058-1B
C-058-1Bx
C-058-1Bxx



C-058-2A
C-058-2Ax
C-058-2Axx



C-058-2B
C-058-2Bx
C-058-2Bxx



C-058-3A
C-058-3Ax
C-058-3Axx



C-058-3B
C-058-3Bx
C-058-3Bxx



C-058-4A
C-058-4Ax
C-058-4Axx



C-058-4B
C-058-4Bx
C-058-4Bxx



C-059-1
C-059-1x



C-059-2
C-059-2x



C-061
C-061-x
C-061-xx



C-062
C-062-x
C-062-xx



C-063
C-063-xx



C-064
C-064-xx



C-066
C-066-xx



C-067
C-067-x
C-067-xx



C-067-T
C-067-Tx
C-067-Txx



C-069
C-069-x



C-070-1
C-070-1x
C-070-1xx



C-070-2
C-070-2x
C-070-2xx



C-071-1
C-071-1x
C-071-1xx



C-071-2
C-071-2x
C-071-2xx



C-072
C-072-xx



C-074
C-074-x



C-076
C-076-x



C-078
C-078-x



C-079-1A
C-079-1Ax
C-079-1Axx



C-079-1B
C-079-1Bx
C-079-1Bxx



C-079-2A
C-079-2Ax
C-079-2Axx



C-079-2B
C-079-2Bx
C-079-2Bxx



C-079-3A
C-079-3Ax
C-079-3Axx



C-079-3B
C-079-3Bx
C-079-3Bxx



C-080-Ta
C-080-Tax
C-080-Taxx
C-080-Taxxx



C-080-TB
C-080-TBx
C-080-TBxx
C-080-TBxxx



C-082
C-082-xx



C-084
C-084-x



C-085-1
C-085-1x



C-085-2L
C-085-2Lx



C-085-2R
C-085-2Rx



C-085-3L
C-085-3Lx



C-085-3R
C-085-3Rx



C-086-1



C-086-2



C-088
C-088-x



C-089
C-089-x
C-089-xx




C-090



C-092



C-111
C-111-x



C-112
C-112-x



C-114
C-114-x



C-115
C-115-x



C-116
C-116-x



C-117-L
C-117-Lx
C-117-Lxx



C-117-R
C-117-Rx
C-117-Rxx



C-118-L
C-118-Lx
C-118-Lxx



C-118-R
C-118-Rx
C-118-Rxx



C-119-L
C-119-Lx
C-119-Lxx



C-119-R
C-119-Rx
C-119-Rxx



C-121-1



C-121-1Ta



C-121-1Tb



C-128



C-129-L
C-129-Lx
C-129-Lxx



C-129-R
C-129-Rx
C-129-Rxx



C-130-L
C-130-Lx
C-130-Lxx



C-130-R
C-130-Rx
C-130-Rxx



C-130-Ta
C-130-Tax
C-130-Taxx



C-130-Tb
C-130-Tbx
C-130-Tbxx



C-132
C-132-x



C-134
C-134-xx



C-135
C-135-x



C-135-Ta
C-135-Tax



C-136-L
C-136-Lx



C-136-R
C-136-Rx



C-137-1
C-137-1x



C-137-2
C-137-2x



C-137-5L
C-137-5L-x



C-137-5R
C-137-5R-x



C-137-7
C-137-7x
C-137-7xx



C-137-8
C-137-8x
C-137-8xx



C-138-L



C-138-R



C-138-Ta



C-138-Tb



C-138-Tc



C-138-Td



C-138-Te



C-138-Tf



C-141
C-141-x



C-149
C-149-x



C-154-D



C-154-L



C-154-R



C-162
C-162-x
C-162-xx



C-170-L
C-170-Lx



C-170-R
C-170-Rx



C-172-L
C-172-Lx



C-172-R
C-172-Rx



C-172-T
C-172-Tx



C-180
C-180-x



C-183



C-183-Ta



C-183-Tb



C-183-Tc



C-184
C-184x
C-184xx



C-185-1
C-185-1x



C-183-Tc



C-185-1Ta
C-185-1Ta-x



C-185-1Tb
C-185-1Tb-x



C-185-2
C-185-2x



C-185-2Ta
C-185-2Ta-x



C-185-2Tb
C-185-2Tb-x



C-185-3
C-185-3x



C-185-4A
C-185-4Ax
C-185-4Axx



C-185-4B
C-185-4Bx
C-185-4Bxx



C-187
C-187-x



C-187-T
C-187-Tx



C-190
C-190-x



C-190-TaA
C-190-TaA-x



C-190-TaLR
C-190-TaLR-x



C-201-1
C-201-1x



C-201-2
C-201-2x



C-201-3
C-201-3x



C-202
C-202-x
C-202-xx



C-203-L
C-203-Lx
C-203-Lxx



C-203-R
C-203-Rx
C-203-Rxx



C-204



C-205-A
C-205-Ax
C-205-Axx



B-C-002



B-C-004-1A



B-C-004-1L



B-C-004-1R



B-C-004-2



B-C-004-Ta



B-C-004-Tb



B-C-004-Tc



B-C-020



B-C-020-T

B.1.2 Regulatory Signs



R-001
R-001-x
R-001-xx



R-001-Ta
R-001-Tax
R-001-Taxx



R-001-Tb
R-001-Tbx
R-001-Tbxx



R-001-Tc
R-001-Tcx
R-001-Tcxx




R-002
R-002-x



R-003
R-003-x
R-003-xx



R-004
R-004-x
R-004-xx




R-010




R-012
R-012x
R-012xx



R-012-T



R-014-L



R-014-R



R-015-L
R-015-Lx
R-015-Lxx



R-015-R
R-015-Rx
R-015-Rxx



R-016-2
R-016-2Lx



R-016-2R
R-016-2Rx



R-017-2



R-018
R-018-x



R-019-1
R-019-1x
R-019-1xx



R-019-2
R-019-2x
R-019-2xx



R-019-3
R-019-3x
R-019-3xx



R-019-Ta
R-019-Tax
R-019-Taxx



R-019-Tb
R-019-Tbx
R-019-Tbxx



R-019-Tc
R-019-Tcx
R-019-Tcxx



R-019-Td
R-019-Tdx
R-019-Tdxx



R-020
R-020-x



R-022-1
R-022-1x
R-022-1xx



R-023
R-023-x
R-023-xx



R-025-L




R-025-R



R-056-1
R-056-1x




R-082-L
R-082-Lx



R-082-R1
R-082-R1x



R-082-R2u
R-082-R2
R-082-R2x



R-083-L



R-083-R



B-R-101-1



B-R-101-2



B-R-101-Tb



B-R-101-Tc

B.1.3 Other Signs



P-081-1



P-081-2



P-081-Ta



P-081-Tb



P081-Tc



W-132-1u
W-132-1
W-132-1x



W-132-1Tu
W-132-1T
W-132-1Tx



C-186




C-186-Ta



C-326
Hinged



C-326-OL
Series



Zx-030

Note: Those wishing to use Z series signs on Provincial roadways shall first obtain Ministry permission and the Ministry's specification sheets.