ACCESS · INDIGENOUS SKILLS 4 SUCCESS

Roadbuilding foundations · Teaching and answer guide

Lesson sequences, answer guidance, evidence criteria and technical handoff.

Classroom teaching edition · 29 October 2026 · Technical review and pilot pending

Contents

1. Unit 1 · Answer and teaching guidance
2. Unit 2 · Answer and teaching guidance
3. Unit 3 · Answer and teaching guidance
4. Unit 4 · Answer and teaching guidance
5. Unit 5 · Answer and teaching guidance
6. Unit 6 · Answer and teaching guidance
7. Technical review and delivery record

Unit 1 · Answer and teaching guidance

Use 10 minutes for source/measure vocabulary, 20 for LA1-01–02, 25 for LA1-03–04, 25 for LA1-05–06, and 10 for revision. Prepare I1–I5 on paper and an actual device turn for each learner. The public-source register and retained extracts make the lesson workable offline; online retrieval remains unobserved until performed.

Task	Expected evidence and useful feedback
LA1-01	Employment is 246,750 people in B.C. construction in 2024. Full-time share is 12 percentage points above the all-industry figure. 87,280 is forecast construction openings over 2025–2035, not guaranteed paving jobs. I1b's categories sum to 427 statistical locations; `175 − 63 = 112 locations`; `175 ÷ 427 × 100 = 40.983606…%`, or **40.98%**. The road-construction classification includes highways, streets and bridges. Locations are not unique companies or workers; size ranges must not be used to estimate total employees. Comparing this location count with all-construction employment mixes measure, scope and period.
LA1-02	A retained note identifies title, WorkBC/Province of B.C., URL, access date, metric/year and any change. Observe locating, saving and reopening independently of the accuracy of the paper answer.
LA1-03	I2 supports selected orientation requirements. I3 explains the document system, but the actual signed contract and relevant amendments/special provisions are needed to establish its applicable edition. I4 identifies the public funders and contractor. I3b confirms End Product Specification in the 2006 clause; it does not establish every old note's intended usage. Profit and a separate unexplained note still require further evidence. A register must not silently label a specification "law."
LA1-04	`215.19 + 385.58 = $600.77 million`. Federal fraction `215.19 ÷ 600.77 × 100 = 35.819032…%`, or **35.82%**. The provincial share is **64.18%** after rounding. The total exceeds $600 million by $0.77 million. Province is the recorded contracting authority; Canada and B.C. are reported funders; Kicking Horse Canyon Constructors is the awarded contractor. The source does not identify profit.
LA1-05	Both recovery pathways are supported. No matched environmental winner is established. A valid grid marks missing quantities/designs, production factors, distances/modes, construction impacts, maintenance schedules, use-stage assumptions and recovery/disposal scenarios. The proposed common service is the 50 m × 6 m route for 20 years; that is a comparison brief, not a verified design.
LA1-06	A per-tonne factory result has a different unit and boundary from a whole-route life-cycle result. Different required quantities may change the comparison. A useful request specifies equal function, service period, approved design quantities, included stages, current geography-relevant data, maintenance and end-of-life assumptions, uncertainty and reviewer. Do not reward an invented emissions calculation.

Worked conclusion: "Both asphalt and concrete have documented material-recovery pathways. The supplied information does not establish which option has lower whole-life emissions for the same 50 m by 6 m route over 20 years. A comparison needs approved pavement quantities, production and transport data, construction and maintenance assumptions, and end-of-life treatment. A factory result per tonne cannot establish the proposed whole-route claim. We can request comparable evidence before recommending an environmental preference."

Evidence criteria and technical handoff

Occupational learning task	Local evidence criterion	Status after successful classroom work
A1.6 · Industry statistics	Name publisher/period/measure/scope; compute valid comparisons; distinguish employment, statistical locations and unique employers	Dated construction employment and road-industry business-location evidence demonstrated; no asphalt-only unique-employer count or current qualification outcome claimed
A1.8 · Regulations and funding	Distinguish a selected legal requirement, contract reference and public funding record; identify actual applicability questions	Document interpretation demonstrated; EPS is defined as End Product Specification in the 2006 clause; current project applicability and the historical outline's intended use of the label still need provider/context confirmation
A1.9 · Environmental comparison	Use evidenced recovery pathways, a common functional question and explicit boundaries; reject an unsupported whole-life percentage	Bounded comparison reasoning demonstrated; no project-specific environmental ranking or technical approval claimed

These are locally authored evidence criteria. The source alignment and detailed technical-review items are in the research and handoff records. Keep **Not observed** separate from **Not yet demonstrated**; provide a new dated table or a changed claim for a retry rather than asking learners to copy the key. Individual evidence includes authored text, an observed explanation, the calculation and actual digital actions where attempted.

Unit 2 · Answer and teaching guidance

Suggested 75 minutes: 10 for purpose and vocabulary, 15 for chronology, 15 for materials/categories, 15 for paired labels, 15 for independent caption and 5 for reflection. Supply H1–H4 and paper or accessible drawing tools. Model observation versus interpretation before using the photograph description. No image or private archive is required.

Task	Expected evidence
LA2-01	312 BCE Via Appia development begins; 1942 Alaska pioneer road completed; 1943 permanent location completed; 1946 Canadian portion responsibility transferred; 1948 civilian non-military opening; 1956 U.S. highway legislation. “Pioneer road” and “permanent location” are different milestones. Chronology alone cannot establish consultation, effects or all perspectives.
LA2-02	Materials: earth, cut stone, gravel, timber logs, concrete, asphalt mixture. Asphalt cement is the bituminous binder in asphalt; Portland cement is used in the cement-based binding system in concrete. Methods: closely laid crosswise logs; delivery/placement/compaction. Purposes: moving timber, military access, travel to a community facility. Accept an explanation that different designs/materials can serve the same purpose. A photo question might concern date, location, scale, layers, use or author.
LA2-03	Observable: logs across a route; truck in background; wet-looking appearance in the supplied description. Possible corduroy construction is a supported interpretation. Logging purpose, owner, actual moisture condition, date and location are not established. The truck does not prove logging.
LA2-04	H2 supports the specific wartime-access explanation. It does not support a universal war-only claim; H1 and H3 also identify trade and daily movement. `1948 − 1942 = 6 years`. H2 records work/responsibility milestones within that interval.
LA2-05	One panel distinguishes timber/crosswise-log method from logging purpose. The other gives mixture delivery, paver/screed placement and roller compaction with preparation/checks acknowledged. Do not score drawing polish or accept an invented operating setting.
LA2-06	A valid caption integrates a correct date with a defined event, distinguishes method/material/purpose, gives evidence for demand and names a limitation. It may discuss public-record limits without asking learners to supply cultural knowledge.

Model caption: “The Alaska Highway's pioneer road was completed in 1942 as a wartime land-access project; its permanent location was completed in 1943. Roads can later support other uses, including civilian travel and trade. Material, method and purpose describe different things: timber logs are a material, corduroy is a construction form, and logging is a road use. Modern asphalt paving combines manufactured mixture, delivery, placement and compaction. These examples show changes in techniques and needs, but they do not establish a single history for every road or describe every community's experience. A local account needs its own evidence and appropriate permission.”

Occupational learning-task evidence

Learning task	Activities	Locally authored criterion
A2.1 · Evolution of roads	LA2-01, LA2-06	Sequence dated examples and state what evolved without a universal-origin claim

Learning task	Activities	Locally authored criterion
A2.2 · Products and application methods	LA2-02, LA2-05	Distinguish earth/stone/gravel/wood/asphalt/concrete and explain the binder distinction at introductory level
A2.3 · Logging and corduroy roads	LA2-02, LA2-03, LA2-05	Distinguish purpose from construction form and avoid unsupported photographic inference
A2.4 · Modern placement	LA2-05	Explain delivery, placement/screed and compaction as broad functions, with preparation/checks
A2.5 · Rationale for road growth	LA2-04, LA2-06	Explain a supported wartime case, post-war context and movement-of-goods purpose without a single-cause generalization

Offer a partly ordered timeline, a word bank or a dictated first draft when useful, recording the support. For a retry, change one event description or give a new category statement. A technical reviewer should check the introductory material descriptions and provider relevance; a local history contribution requires its own sourcing and permission, not instructor inference.

Unit 3 · Answer and teaching guidance

Use 15 minutes for ingredients and the flow visual, 15 for plant comparison, 15 for product clarification, 20 for recycling routes, 10 for the counter model and 15 for revision/digital note. Prepare 100 counters or a labelled paper grid; count categories, not a real mixture. Provide an actual device turn for LA3-07 if Digital is assessed.

Task	Expected evidence
LA3-01	Asphalt cement and asphalt binder name the binding material in this introductory context. Aggregate is mineral material; asphalt binder binds the asphalt mixture; process fuel supplies energy and must not be assumed to be an ingredient. “Cement” may refer to asphalt cement or Portland cement. An additive may alter a specified property; its purpose and suitability require the actual product and approved mixture requirements. A pit commonly supplies unconsolidated material; a quarry commonly extracts rock that is processed. Neither source name guarantees suitable aggregate. Source suitability needs specification/material-property evidence.
LA3-02	B indicates batches; D indicates a continuous drum-mix process in the simplified case. Shared stages include supplied materials, proportioning/mixing, storage or loading and haul. A drying drum alone does not distinguish the two. Figure LA-4 shows separate weighed batches versus a continuing measured material stream; some continuous facilities use a separate dryer and continuous mixer.
LA3-03	Ask for full product name/grade, current approved design or project specification, supplier/product confirmation and relevant safety/handling information through the responsible person. The undefined “Group A / C” and “altered oil” labels require an explicit clarification; do not infer a grade or product from them. No grade is approved by the task.
LA3-04	Plant route: recovery/processing → suitable plant input → approved mixture/use. Hot-in-place route: specialist coordinated process works on existing pavement in place. Both need applicable approved process, suitability and quality evidence. Removal is not proof of later reuse.
LA3-05	80%, 15%, 5%; sum 100%. The recovered-mixture category includes more than one constituent, so the model does not isolate total binder content. The counters are not mass or a production recipe.
LA3-06	Remove the unsupported plant-haul label and show the in-place route; retain the idea of recovering/reusing existing material. Identify equipment/process details as pending. Observe each learner's correction and handover.
LA3-07	The learner controls the wording, saves and retrieves a versioned file and explains the distinctions. Paper composition supports Writing but does not demonstrate save/reopen. Figure LA-3: 7 Hopper (holds supplied material); 10 Screed Extension (extends working width); 11 End Gate (helps form the mat edge); 12 High-Speed Rubber Tracks (travel component, not a speed instruction). Figure LA-5 route: hopper receives → slat conveyors move rearward → augers distribute across width → screed places/shapes the mat. Conveying rearward and distributing laterally are distinct functions. Check two selected labels against the photo. Retain model 8680, manual 1033428-SOP, printed p. 3-7 / PDF p. 43, and serial scope 365152 and above. The image does not establish operating settings, current condition or applicability to another machine.

Occupational learning-task evidence

Learning task	Activity	Locally authored criterion
A3.1 · Drum and batch plants	LA3-02	Distinguish process types without classifying by one visible component

Learning task	Activity	Locally authored criterion
A3.2 · Ingredients	LA3-01, LA3-05	Explain aggregate/binder/additive roles and avoid treating fuel or mixed recovered material as a single known constituent
A3.3 · Resources	LA3-01	Distinguish pit/quarry sources and suitability questions
A3.4 · Production liquids	LA3-03	Recognize that grade systems/product labels need current application and supplier confirmation; no operational selection demonstrated
A3.5 · Recycling technology	LA3-04, LA3-06	Distinguish plant reuse, recovery and in-place processes and identify needed evidence
A3.6 · Asphalt train / hot-in-place	LA3-04, LA3-06, LA3-07	Explain a coordinated train and the distinction between placement and specialist in-place recycling

Record grade interpretation and specific plant/recycling practices as requiring qualified technical review. The classroom unit teaches the vocabulary and information decisions with complete cases; it does not establish temperatures, percentages, compatibility, settings or a machine procedure. For a retry, present a different component-based misclassification or an incomplete product request and observe the learner's reasoning.

Teach the photograph as evidence

For Figure LA-3, demonstrate one numbered callout before asking for another. A learner may point, use a magnified view, or name the callout verbally; the same source detail must be identifiable. The adjacent four-row table provides a text route for the selected component names. Keep the full manual page available when a learner asks about another number. Do not infer a function from shape alone or read the word “High-Speed” as an instruction.

The component-reading addition supports A1 equipment vocabulary and introduces I2 terminology. It is not the complete I2 technical unit. The answer-guide activity IDs and A3 criteria remain the same, so the instructor can preserve evidence continuity.

Connect the two drawings to the machine photograph

Use Figure LA-4 with LA3-02, then Figure LA-5 with LA3-07. Have a learner trace and say each material route before writing it. Keep the source figure/page with the explanation. The complete Understanding asphalt learner book provides MS4-03–MS4-06 for additional process comparison, saved notes and checked communication, with separate answer guidance. The source figures and original contributor credits are recorded in the adjacent captions.

Unit 4 · Answer and teaching guidance

Suggested 90 minutes: role mapping 15, safety case 20, licences 15, handover 10, schedule 15 and development/enquiry 15. Allow spoken planning before authored writing. Keep every role-play in the classroom; provide no simulated machine signals. Evaluate observable actions and source distinctions rather than confidence, accent or posture.

Task	Expected evidence
LA4-01	Broad functions and meaningful dependencies: haul supplies mixture; paver places; screed helps control the placed layer; raker supports handwork/finishing; roller compacts; milling removes/profiles existing material. A handover identifies status or information, not an invented signal. W1 authorizes no site access or operation.
LA4-02	Equipment-name knowledge is insufficient workplace-specific orientation. Learner asks for supervisor/contact, relevant hazard and emergency information, task instruction/demonstration and the appropriate communication arrangements. The employer's obligation is not transferred to the learner.
LA4-03	Admission: provider's current intake requirements. Licence: ICBC/applicable legal requirements for the actual vehicle/activity. Competence: appropriate training and assessment records. Assignment: responsible employer/site authorization. Class 5/7 in a provider prerequisite cannot authorize every truck or machine.
LA4-04	Example: “The role map is ready for review, but licensing is still pending. We can print the classroom explanation with that question marked open and ask the responsible person before adding an authorization claim.” Observe the receiver's check-back and each contribution.
LA4-05	18:00–24:00 is 6 h; 00:00–02:00 is 2 h; elapsed 8 h. Subtract 0.5 h = 7.5 paid hours in the fictional record. Add Wednesday 6 h = 13.5 h. Questions may concern overtime, cancellation/travel pay, breaks, fatigue controls or actual schedule arrangements. No legal entitlement follows from these invented inputs.
LA4-06	Collective bargaining is negotiation between an employer and workers represented by a union about employment terms; the applicable parties, agreement and dates must be checked. Forecast demand and attendance do not guarantee hiring, continued work or qualification. Questions identify the actual agreement/terms and role-specific pathway; the goal includes a task, evidence, support, check date and responsible reviewer. A saved/reopened file is separate from a paper enquiry. Do not require sending, personal employment disclosure or joining any organization.

Occupational learning-task evidence

Learning task	Activities	Locally authored criterion
A4.1 · Health and safety	LA4-02	Explain the need for workplace-specific orientation and appropriate clarification
A4.2 · Paving jobs	LA4-01	Distinguish six broad functions and a dependency
A4.3 · Licensing	LA4-03	Separate admission, licence, competence and assignment; identify verification route
A4.4 · Professionalism	LA4-04	Correct an overclaim, give an accurate handover and preserve pending status
A4.5 · Employer responsibility	LA4-02	Identify the employer's orientation/training role without assigning it solely to a worker
A4.6 · Advancement	LA4-06	Make a role-specific learning enquiry and observable development goal

Learning task	Activities	Locally authored criterion
A4.7 · Job security	LA4-05, LA4-06	Explain that demand forecasts and course attendance do not guarantee employment
A4.8 · Organized labour	LA4-06	Explain collective bargaining at introductory level and check agreement parties/dates/applicability
A4.9 · Working conditions	LA4-05, LA4-06	Name conditions and relevant questions without inventing employment or safety rules

Before workplace delivery, a qualified reviewer must confirm role descriptions, current legal/licensing application, provider pathway, workplace safety program and employment/collective-agreement context. This unit supplies the classroom cases and answer criteria; that review is an edition-status requirement, not a request for learners to devise actual operating procedures.

Unit 5 · Answer and teaching guidance

Use 120 minutes: project/document register 15, three-view vocabulary 25, modelled quantity 20, independent check 20, revision 25 and handover 15. Provide the complete P-01/Q-01/SP-01 text, calculator, blank paper and the cross-section visual. No physical measurements of the printed image are valid inputs. Offer unit cards and a partly completed quantity table when needed. Record support.

Task	Expected evidence
LA5-01	Private facility access; Cedar Learning Society owner; Valley Surface Ltd. contractor; community fund contributor. Use/category does not by itself adopt a specification. Actual signed contract and authorized current documents determine applicability.
LA5-02	Plan: 50 m horizontal length/6 m width. Profile: elevation change along centreline. Section: 40 mm calculation-layer thickness. 100.50 m is an elevation relative to the illustrative datum, not a layer depth.
LA5-03	Crown raised transverse form; shoulder road edge area; open ditch drainage channel; curb/gutter contained edge/drainage arrangement; sidewalk pedestrian route; runoff surface-water movement; superelevation cross-slope arrangement on curves; grader equipment. Figure LA-6: granular base supports the asphalt surface; subbase is an additional supporting layer where specified; prepared subgrade is the prepared ground beneath the pavement structure. Other structures exist; the drawing supplies no P-01 design dimensions. Questions may concern outlet, base preparation, approved slope, services or required materials. Do not supply invented design answers.
LA5-04	Thickness 0.040 m; area 300 m²; volume 12 m³; model mass 24 t. Records 8 + 8 + 7.6 = 23.6 t, 0.4 t below the model quantity. Profile rise 0.50 m/50 m=1%. Neither record totals nor an invented factor establish actual placed quantity, thickness, density, acceptance or payment.
LA5-05	Revision C area 360 m²; volume 14.4 m³; model mass 28.8 t. Increases 60 m², 2.4 m³, 4.8 t. Existing record total 23.6 t is 5.2 t below the revised model quantity. Profile rise 0.60 m/60 m=1%. Keep the old record and identify which revision each calculation uses.
LA5-06	Handover includes current revision C, 14.4 m³ geometric model, 28.8 t at fictional 2.00 t/m³, 23.6 t recorded, 5.2 t arithmetic difference, and the limits on a real order or acceptance decision. Each person demonstrates both checks over the two cases.

Model quantity note: “P-01 revision C shows a 60 m by 6 m rectangle with a 0.040 m calculation layer. Area is 360 m² and geometric volume 14.4 m³. At the supplied fictional 2.00 t/m³ factor the model mass is 28.8 t. The unchanged classroom records total 23.6 t, a 5.2 t difference. I checked units and recalculated from the new length. These model values do not establish an actual order, approved density or acceptance result.”

Occupational learning-task evidence

Learning task	Activities	Locally authored criterion
A5.1 · Project categories	LA5-01	Distinguish use from jurisdiction and avoid treating categories as mutually exclusive
A5.2 · Owner types	LA5-01	Recognize provincial/federal/municipal/private possibilities and distinguish owner/funder/contractor in the case

Learning task	Activities	Locally authored criterion
A5.3 · Common work/forms	LA5-02, LA5-03	Describe listed road forms, drainage vocabulary and grader-equipment distinction
A5.4 · Specifications	LA5-01, LA5-05	Find the applicable exercise document and revision; identify real contract applicability as a separate check
A5.5 · Cross-section/preparation	LA5-02–LA5-04	Read conceptual layers and identify unanswered civil/preparation questions without treating the sketch as design
Bridge toward F2/F3	LA5-04–LA5-06	Demonstrate drawing-reading and quantity arithmetic with stated assumptions; no F2/F3 practical competence or road-design approval claimed

The technical reviewer must confirm the conceptual road terminology, drawing conventions, selected quantity model, appropriate metric/imperial bridge and any later use of real specifications or acceptance limits. Do not substitute these classroom numbers for a project design. A retry can change one dimension, record unit or revision; keep enough information to calculate and explain the result independently.

Unit 6 · Answer and teaching guidance

Use 90 minutes: claim reading 15, material/lightweight-fill discussion 15, cost calculation 10, supplier enquiry 10, option table 20, changed condition 10 and brief/check 10. Supply N1–N8 and the retained public-source excerpts. Learners need no product samples, site data or external accounts. Distinguish an evidence-supported mechanism from a project performance prediction.

Task	Expected evidence
LA6-01	Paving-stone permeability depends on the complete system; porous asphalt with a reservoir still needs site/drainage design and maintenance; recycling alone cannot establish total impact. Each revision names a condition and a question rather than simply adding “may” to a vague claim.
LA6-02	`$1,145,000 – $633,000 = $512,000`. Limits include historical 2016/2017 context, California/U.S. geography/currency context, project-specific quantities/design, missing installation/overhead/profit and no current B.C. supplier quotes. Technical suitability depends on site/design requirements, not the cheapest listed total. The example concerns lightweight fill; that role cannot be relabelled as approved pavement sub-base without design and material evidence.
LA6-03	Questions identify actual product/system, intended use, relevant tested performance, maintenance, compatibility and approval. Pattern questions include access/visibility and permission for any protected imagery. No universal epoxy, colour or pattern performance is accepted without evidence.
LA6-04	Porous asphalt relates to water management, subject to site/loading/drainage/maintenance study. Coloured asphalt may relate to wayfinding; it does not answer infiltration or structural needs by colour alone. EPS geofoam relates to embankment/load conditions that have not been established for this courtyard. Accept different investigation shortlists when evidence and limits are explicit. Appropriate review may include qualified pavement/civil/geotechnical/design professionals and the facility's maintenance decision-maker.
LA6-05	Lack of a specialized-maintenance commitment is relevant to clogging/maintenance risk in the porous-asphalt reference. A reasonable revision makes maintenance feasibility a condition for investigation or postpones that option. It does not establish an alternative's suitability.
LA6-06	The brief recommends an investigation, with a known mechanism, a case-specific unknown, source date and next decision. Reader can distinguish a recommendation to study from permission to construct. Record actual file actions separately.

Model brief: “For the fictional 600 m² courtyard, investigate whether a porous-asphalt/stone-reservoir system could meet the surface-water and loading requirements. FHWA's2015 brief describes the mechanism and identifies clogging and specialized maintenance as considerations. We have no infiltration/geotechnical results or maintenance commitment, so we cannot recommend construction. First obtain site/design review and a feasible maintenance plan. Evaluate wayfinding separately: colour may help a communication purpose but does not establish drainage performance. Keep environmental comparisons within a defined life-cycle boundary and use project-specific information before ranking options.”

Occupational learning-task evidence

Learning task	Activities	Locally authored criterion
A6.1 · Green roads: paving stones, porous asphalt, recycling	LA6-01, LA6-04	Explain three different mechanisms and conditions; avoid universal “green” claims
A6.2 · Epoxy/coloured/modified materials	LA6-03, LA6-04	Distinguish product families and request performance/application evidence
A6.3 · New sub-bases/pumice	LA6-02	Identify pumice in a bounded historical lightweight-fill comparison and state suitability/data limits
A6.4 · Floating roads/foam	LA6-02, LA6-04	Explain lightweight-fill purpose and EPS term without implying flotation or generic-foam substitution
A6.5 · Added-value enhancements/street print	LA6-03, LA6-06	Separate visual purpose, technical evidence and permission

A qualified reviewer must check the material descriptions, local suitability questions, dated-reference use and terminology before technical delivery. These sources are evidence for mechanisms and questions, not current B.C. design approval. A retry can use an unfamiliar marketing claim with a different missing condition. Ask learners to identify what evidence would change their conclusion.

Technical review and delivery record

Edition: Asphalt paving · Roadbuilding foundations, 29 October 2026. **Current status:** classroom units authored; independent qualified technical review, ACCESS delivery agreement, local co-design and classroom pilot not yet recorded. No external messages have been sent as part of this preparation.

What the reviewer receives

The six units contain learner readings, complete fictional inputs, worked models, individual and group tasks, separate keys and local evidence criteria. The research register preserves current public-source facts, dated technical references and unresolved questions. The 68-row competency map distinguishes authored Line A work from later occupational scope. Classroom outputs can support a learning record; they do not substitute for workplace practical assessment or equipment endorsement.

Program hours and pathways: keep three records separate

Record	Confirmed information	What is not confirmed by it
Supplied November 2014 program profile, PDF 2–3	120 technical-training hours; four weeks based on 30 hours/week; separate workplace/endorsement and assessment pathway information	Current regulator requirements, the chosen provider's current delivery agreement or ACCESS cohort timetable
IUOE Local 115 public provider page retrieved 29 October 2026	Four weeks at Maple Ridge; course dates to be announced; exact page statement “Total accumulated hours equivalent to 140” with spacing normalized here only in prose	Regulator approval of every pathway statement; the meaning/allocation of accumulated hours; ACCESS-specific dates, funded seats or agreed delivery
Proposed classroom learning sequence in this book	555 minutes, or 9 h 15 min, across six units including supported foundation practice	Technical-training credit, an official program duration or complete Line A qualification assessment

The supplied outline assigns 3% of historical technical time to all of Line A. Applying that share to 120 hours gives 3.6 hours, not 3.6 hours for A1 alone. The new classroom practice time has a different purpose and must not be substituted into a regulator or provider schedule without agreement. The 140-hour provider statement is now verified as a published statement; its relationship to the historical 120-hour profile remains a pathway question.

The IUOE page includes course-completion and credential/endorsement language alongside other training references. Retain the wording in the evidence record and obtain written clarification from the responsible provider/regulator before describing the current qualification pathway. A Class 5/7 provider admission condition is separate from the driver's licence or authorization required for a particular workplace vehicle/activity. Do not use a failed guessed webpage request as evidence that a regulator standard has changed.

Review questions by unit

Area	Concrete review item	Proposed qualified reviewer / evidence needed
A1 industry statistics	Confirm use of WorkBC construction employment and Statistics Canada's December 2025 NAICS 237310 statistical-location counts. Check that learners distinguish this measure from unique employers, people and asphalt-only activity. Retain the machine reference-period field alongside the published table title.	Provider/trade curriculum lead; retained official table/metadata and activity evidence
A1 requirements/funding	Confirm use of OHS 3.22–3.25, current contract-specification reading and actual project applicability. The 2006 specifications explicitly define EPS as End Product Specification in 502.03.01, PDF 297. Confirm the historical outline A1 label's intended relationship with that definition and current provider context; keep this meaning distinct from expanded-polystyrene geofoam.	Qualified instructor/project-specification reviewer; regulator/issuer clarification where needed
A1 environmental comparison	Check recovery-pathway descriptions and functional/boundary reasoning. A matched current project life-cycle comparison requires approved equivalent designs and complete assumptions; none is claimed in the learner task.	Pavement/environmental specialist; matched project data if a material ranking is to be assessed
A2 history	Check material/method descriptions, local relevance and the use of public historical accounts. Any Nation-specific contribution requires appropriate invitation/permission and attribution.	Trade instructor and relevant local knowledge holders where a local contribution is invited
A3 technology	Review batch/drum distinctions, plant versus in-place recycling, role of liquids/additives and grade-language exercise. Supply current approved product examples if deeper grade interpretation is required.	Qualified asphalt plant/paving instructor or specialist
A4 workers	Confirm current duties, role boundaries, licensing/endorsement route, employment conditions and any agreement used in delivery.	Provider lead, employer safety lead and relevant licensing/labour sources
A5 road documents	Check plan/profile/section language, conceptual layer/edge diagram, assumed rectangular model and any later real quantity/acceptance document. Fictional 2.00 t/m³ is only a teaching conversion.	Civil/pavement professional and qualified trade instructor
A6 trends	Check product-family descriptions, porous-system distinctions, historical lightweight-fill data and local study/approval questions. The 2017 manual is not a current B.C. standard.	Civil/geotechnical/pavement reviewer with relevant current expertise
Practical progression	Confirm B1/site induction and equipment-specific prerequisites before any workplace or machine activity; identify responsible observers and approved assessment records.	Provider/employer authorized training and safety personnel

Sign-off record

Item/unit and revision	Reviewer name/role	Source/application checked	Required change	Date and disposition
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____
_____	_____	_____	_____	_____

Disposition choices: accepted for the stated classroom use; accepted with recorded conditions; revise and resubmit; outside reviewer's scope. No names or approvals are prefilled. A completed review must identify its scope; it cannot silently become approval for all 68 competencies.

Pilot evidence

Before a wider release, record the cohort/context, actual durations, access arrangements, confusing terms, activity evidence, calculation errors, learner feedback and revisions. Ask for consent before retaining identifiable work. Use ordinary learning evidence rather than pressure to disclose personal experience. Record which activities were actually observed and which need another opportunity. The facilitator should have the answer guide and a route to qualified technical clarification.