agents. The water in the emulsion is liberated in the form of steam when it is mixed with the hot aggregate, breaking the emulsion and causing a foaming action. Mix temperatures leaving the plant have ranged from 185°F to 240°F (85°C–115°C).

Resources

1. *Asphalt Cold Mix Manual,* MS-14. The Asphalt Institute. Lexington, KY.
2. *Asphalt Emulsion,* MS-19. The Asphalt Institute. Lexington, KY 1989.
3. *Asphalt in Hydraulics,* MS-12. The Asphalt Institute. Lexington, KY 1976.
4. *Asphalt Use in Water Environments.* IS-186. The Asphalt Institute. Lexington, KY.
5. Hanson, Douglas I., James, Robert, NeSmith, Christopher. *Tire/Pavement Noise Study, National Center for Asphalt Technology Report 04–02.* Auburn, AL 2004.
6. *Porous Asphalt Pavements, Information Series 131.* National Asphalt Pavement Association. Lanham, MD 2003.

Photo/Illustration Credits

Figure Number	Description	Contributor
1.2	Hot Mix Asphalt Manufacturing Facility	Gencor Industries, Inc.
2.51	Toughness and Tenacity Equipment & Operation	SemMaterials, L.P.
3.1	Sources of Natural Aggregates in U.S.	United States Geological Survey (USGS)
3.2	Rock Quarry Excavation	The Plantmix Asphalt Industry of Kentucky, Inc.
3.3	Aggregate Segregation	National Stone, Sand and Gravel Association
4.29	Resilient Modulus Test Set-up	SemMaterials, L.P.
4.35	Hamburg Wheel-Tracking Device	SemMaterials, L.P.
4.39	Typical APA Test Results	Asphalt Pavement Association of Oregon
7.2	Flow of Material through a Batch Plant	Terex Roadbuilding
7.3	Components of a Modern Drum-Mix Plant	National Highway Institute (NHI)
7.4	Flow Process through a Drum-Mix Plant	National Highway Institute (NHI)
7.7	Bin for Reclaimed Asphalt Pavement	James A. Scherocman Consulting Engineer
7.10	Knock-Out Box on Drum-Mixer Plant	James A. Scherocman Consulting Engineer
7.13	The Internal Components of a Baghouse	Terex Roadbuilding
7.14	Fines-Return System on Drum-Mix Plant	Asphalt Materials, Inc.
7.15	Fines-Return System with Storage Silo	Murphy Pavement Technology
7.16	Continuous Weigh Pod for Baghouse Dust or Filler on Drum Plant	Asphalt Materials, Inc.
7.17	Self-Erecting Silo with Weigh Scale in Silo	Terex Roadbuilding
7.18	Stationary Silos over Truck Scale	Asphalt Materials, Inc.
7.23	Parallel-Flow Drum-Mixer Flow	Astec Industries, Inc.
7.24	Counterflow Drum-Mixer Flow	Astec Industries, Inc.
7.25	Separate Dryer and Mixer Flow	Astec Industries, Inc.
7.26	Double-Barrel Unitized Dryer/Mixer Flow	Astec Industries, Inc.
7.28	Computerized Cold-Feed Calibration Screen	Terex Roadbuilding
7.29	Computerized Mix Formula Screen	Terex Roadbuilding
7.32	Mixing Tips/Double-Barrel Unitized Dryer/Mixer Plant	Astec Industries, Inc.

Figure Number	Description	Contributor
8.1	Distributor Applying a Prime Coat	E.D. Etnyre & Co.
8.2	Standard Dump Truck	James A. Scherocman, P.E. Consulting Engineer
8.6	Proper Method for Breaking the Load	James A. Scherocman, P.E. Consulting Engineer
8.8	Material Transfer Device (MTD)	James A. Scherocman, P.E. Consulting Engineer
8.9	Windrow Paving	James A. Scherocman, P.E. Consulting Engineer
8.11	Schematic of Asphalt Paver	Volvo Construction Equipment
8.13	Track-Mounted Laydown Machine	James A. Scherocman, P.E. Consulting Engineer
8.15	Ultrasonic Noncontact Sensors for Material Control	Murphy Pavement Technology
8.16	Free-Floating Screed	Volvo Construction Equipment
8.17	Screed with Varible-Width Extentions	James A. Scherocman, P.E. Consulting Engineer
8.19	Improperly Aligned Screed Extension	James A. Scherocman, P.E. Consulting Engineer
8.21	Thirty-Foot Mobile Reference	James A. Scherocman, P.E. Consulting Engineer
8.23	Distance Required for Screed Change to Fully Occur	Volvo Construction Equipment
8.24	Placement of Kraft Paper Bond Breaker on a Transverse Joint	James A. Scherocman, P.E. Consulting Engineer
8.25	Applying Tack Coat on Transverse Joint	James A. Scherocman, P.E. Consulting Engineer
8.26	Segregation Along Outside Edge of Mat	James A. Scherocman, P.E. Consulting Engineer
8.29	Asphalt Curb Machine	Gomaco Corporation
8.30	Roller Mounted with Pipe for Rolled-In Joints	Plantmix Asphalt Industry of Kentucky, Inc.
8.31	Rolled-In Rumble Strips	Plantmix Asphalt Industry of Kentucky, Inc.
8.32	Milled-In Rumble Strips	Plantmix Asphalt Industry of Kentucky, Inc.
9.5	Static Steel-Wheel Roller	Sakai America, Inc.
10.2	Stockpile Sampling	Martin Marietta Materials, Inc.
10.5	Truck Sampling	Murphy Pavement Technology
10.9	Temperature Measurements	Murphy Pavement Technology
12.6	Patcher Truck	H.D. Industries, Inc.
12.7	Medium-Size Milling Machine	Wirtgen America, Inc.
12.8	Small-Size Milling Machine	Wirtgen America, Inc.
12.10	Spray-Injection Patching Machine	Crafco, Inc.
12.13	Placing Crack Filler with Hand Wand	Crafco, Inc.
12.14	Preparation of Surface with Power Sweeper	TYMCO International, LTD.
12.19	Truck-Attached Mechanical Spreader	ThorWorks Industries, Inc.

Figure Number	Description	Contributor
12.20	Self-Propelled Mechanical Spreader	E.D. Etnyre & Co.
12.24	Microsurfacing Machine	Murphy Pavement Technology
12.25	Microsurfacing Spreader Box	SemMaterials, L.P.
12.26	Rut-Filling Box	SemMaterials, L.P.
13.5	Placement of Strip Membrane	Cygnus Business Media
13.6	Onsite Asphalt Rubber Blending Equipment	Rubber Pavements Association
13.7	Large High Capacity Milling Machine	Caterpillar Inc.
13.8	Medium Sized Milling Machine	Wirtgen America, Inc.
13.9	Tungsten Carbide Milling Teeth	Wirtgen America, Inc.
13.10	Micromilled Surface	Murphy Pavement Technology
13.12	Surface Recycling Pre-heaters	Dustrol Inc.
13.13	Close up of Scarifying Tines	Dustrol Inc.
13.14	Repaver	Cutler Repaving, Inc
13.15	Repaver Mixer	Cutler Repaving, Inc.
13.16	Multistage Remixing Train	Martec Recycling
13.18	Windrow of Material behind First Unit	Pyrotech Asphalt Equipment Co.
13.21	Single-Unit CIPR Machine	Murphy Pavement Technology
13.25	Laboratory Asphalt-Foaming Plant	Wirtgen America, Inc.
13.26	Modern FDR Reclaimer	Asphalt Busters
13.27	Pulverized Material Exiting the Reclaimer	Caterpillar Inc.
13.28	Reclaimer with Nurse Truck	Caterpillar Inc.
13.29	Motor Grader Shaping Reclaimed Surface	Asphalt Recycling & Reclaiming Association (ARRA)
13.30	Reclaimed Surface Before Compaction	Asphalt Recycling & Reclaiming Association (ARRA)
14.3	Deep Saw Cut with Reservoir	Minnesota Department of Transportation
14.5	Secondary Reflection Crack	Minnesota Department of Transportation
14.9	Crack Pattern of Cracked and Seated Pavement	Badger State Highway Equipment, Inc.
15.2	Blade Mixing	Murphy Pavement Technology
15.3	Rotary Mixer—Pulvimixer Type	BOMAG Americas
15.5	Cold Mix Continuous Mixing Facility	Pugmill Systems, Inc.
15.10	Placing HMA Underlayment in Southern Kansas	Jerry Rose, University of Kentucky College of Engineering
15.11	Placing Underlayment by Backdumping and Spreading	Jerry Rose, University of Kentucky College of Engineering
15.12	Asphalt Running Track	ThorWorks Industries, Inc.
15.13	Asphalt Tennis Court	ThorWorks Industries, Inc.

Index

A

Absorbed asphalt content (P_{ba}), 173
Absorption, of an aggregate, 128
AC (Asphalt Cement) system, 41
Acceptance criteria, of HMA construction projects
  general compaction requirements, 501–506
  historical acceptance, 500
  modern, 500–501
  statistical acceptance, 506–512
Acceptance practices, 447
Acceptance testing
  aggregate angularity, 493–494
  asphalt content and gradation, 493
  compaction, 494–496
  of ride quality, 496–498
  for thickness, 496
  volumetric properties, 494
Additives and modification, of asphalts
  rationale of use, 86
  tests for, 92–98
  types, 86–91
Aggregate absorption, 170
Aggregate additives
  antistrip additives, 154–155
  fibers, 155–156
  mineral filler, 152–153
  roofing-shingle scrap, 156
  scrap tires (ground rubber), 156
Aggregate angularity, 465
  acceptance for, 493–494
Aggregate cleanliness, 131
Aggregate coatings, 131
Aggregate dryer, 319–322
Aggregate gradation, 464–465
Aggregate packing properties, in HMA
  CA, FA_c and FA_f ratios, 216
  PCS percentage, 215
Aggregates, for hot mix asphalt (HMA) mixture
  classification, 112
  origin of bedrock, 111–113
  production, 117–119
  sources of, 113–116
Aggregates for HMA, composite analysis
  calculation of surface area, 145–146
  composite-aggregate size designations, 135–136
  composite-aggregate size fractions, 136
  gradation adjustments for specific gravities, 144–145
  gradation blending calculations, 139–144
  gradation types, 134–135
  power gradation curve, 136–139
Aggregates for HMA, properties, 112
  deleterious substances, 130–132
  freeze-thaw/weathering resistance, 130
  particle shape and surface texture, 122–126
  particle size and grading, 121–122
  pore structure, porosity and absorption, 128
  segregation, 120
  specifications, 132–133
  specific gravity, 128–130
  stone matrix asphalt (SMA) aggregate quality requirements, 133
  toughness, 126–128
Aggregate spreader, 597–599
Aggregate stockpiling facility, 315–317
Air-blown asphalts, 26, 727
  properties and specifications, 83–85
Air-voids, 129, 168, 172
  in compacted mixture, 184–185
  testing for, 468
Akkadian *asphaltic,* 3
Alligator (fatigue) cracking, 164, 536, 542–543

American Association of State Highway and Transportation Officials (AASHTO) specifications
AASHTO M 323, 213
AASHTO M 20 asphalt binder, 40
AASHTO M 43 (ASTM D 448), 122
AASHTO Materials Reference Laboratory (AMRL), 449
AASHTO M 320 binder specifications, 63–65
AASHTO MP 323, 121
AASHTO PP 41, 217
AASHTO PP 48, 192
AASHTO R 35, 189, 194
AASHTO T 19, 220, 225
AASHTO T 40, 463
AASHTO T 110, 720
AASHTO T 164, 210
AASHTO T 166, 220
AASHTO T 209, 211, 467
AASHTO T 246, 204
AASHTO T 247, 204
AASHTO T 283, 196, 221
AASHTO T 292, 261
AASHTO T 304, 466
AASHTO T 307, 261
AASHTO T 308, 210, 657
AASHTO T 324, 237
AASHTO T 165 and T 167, 227
AASHTO T 89 and T 90 (ASTM D 4318), 131
AASHTO T 11 (ASTM C 117), 132
AASHTO T 84 (ASTM C 128), 128–129
AASHTO T 85 (ASTM C 127), 128–129
AASHTO T 96 (ASTM C 131), 127
AASHTO T 104 (ASTM C 88), 130
AASHTO T 112 (ASTM C 142), 132
AASHTO T 176 (ASTM D 2419), 131
AASHTO T 195 (ASTM D 2489), 338
AASHTO T 327 (ASTM D 6928), 127
AASHTO T 166 (ASTM D 2726) procedure, 179–180
AASHTO T 209 or ASTM D 2041, 176–178
American Concrete Institute (ACI), 449
Anionic emulsified asphalts (ASTM D 977), 77
Antioxidants, 91
Antistripping additives, 91–92
Apparent specific gravity (G_{sa}), 129
of aggregate, 175–176
AR (Aged Residue) system, 41
Arizona Department of Transportation method, for binder content, 729
Asphalt, *see also* PG asphalt binder tests; *specific asphalts*
additives and modifications, 86–98
aging effects, 46–47
American Society for Testing and Materials (ASTM) definition, 23
background, 3–4
behavior in different temperatures, 44–47
binders, 8
cement, 7–9, *see also* Tests, for asphalt cement
early application of, 3
frequently asked questions, 106
historical milestones, 5–6
natural, 7
pavements, *see* Pavements
paving mixtures, 10–12
refining methods, 3–4
safety procedures for binders, 107
sampling, 101–102
surface treatments, 12
Asphalt absorption (P_{ba}), 181
Asphalt binder, 186
for chip sealing, 590–591
selection by Hveem method, 205
selection by Marshall method, 200
selection for hydraulic purpose, 729–730
Asphalt binder sampling, 463
Asphalt built-up roof, 745
Asphalt concrete floors, 751
Asphalt content
defined, 173
in the mixture, effect of, 169–170
testing for, 466–467
Asphalt coring, 462
Asphalt distributor, 594–597
Asphalt foaming, 27
Asphalt Institute Mix Design Program SW-2, 198
Asphalt Institute Mix Design Technologies Certification Program for Technicians, 449
Asphalt Institute vacuum viscometer, 28–29

Asphalt mastic floors, 751
Asphalt mastic seals, 732–733
Asphalt Pavement Analyzer (APA), 237–240
Asphalt properties, in RAP mixture, 211–213
Asphalt proprietary mixes, 573
Asphalt retention, of geotextiles, 630
Asphalt roll roofing, 744–745
Asphalt shingles, 744
Asphalt surface treatments
  cape sealing, 613–614
  chip sealing, 589–604
  microsurfacing, 610–613
  pavement surface preparation, 587
  sand sealing, 614
  slurry sealing, 605–610
  spray applied sealers, 588–589
Asphalt temperatures, control of
  mixing, 99–100
  precautions, 100–101
  spraying, 100
Asphalt-treated permeable base (ATPB)
  description, 228
  mix design characteristics and procedures, 228–229
Asphalt Vibratory Compactor, 237
Asphalt weigh bucket, 336
ASTM C 29, 225
ASTM C 136 (AASHTO T 27), 121
ASTM D8, 635
ASTM D 140, 463
ASTM D 1188, 174
ASTM D 1559, 198
ASTM D 1560, 204
ASTM D 1561, 204
ASTM D 2041, 211, 467
ASTM D 2172, 210
ASTM D 2726, 180, 225
ASTM D 3666, 449
ASTM D 4552, 589
ASTM D 4694, 535
ASTM D 4867, 196
ASTM D 5821, 466
ASTM D 6307, 210, 657
ASTM D 6390, 222
ASTM D 6433, 536
ASTM D 1557/AASHTO T 180, 743
ASTM D 1075 and D 1074, 227
ASTM D 946 asphalt binder, 40
ASTM D 698 or D 1557, 254
ASTM E 274, 532
Athletic or recreational facility, using HMA
  basic design, 741
  pavement thickness, 742–743
  types of facilities, 740–741
Atmospheric residue, 25

B

Backer rods, 584–585
Baghouse dust, usage of, 326
Bailey Method, 215
Ballast thickness, 737
Batch production process, 309–311
  aggregate gradation control, 332–336
  asphalt content control, 336–337
  mixing/coating, 337–338
  production problem-solving guide, 353–355
  recycled mix production, 338–339
Batch-type pugmills, 719
Beach sands, 114
Beam theory, 54
Belly-dump trailers, 700
Belt-type conveyors, 318
Bending beam rheometer (BBR), 54
  stiffness, 212
  tests, 211
Benkelman Beam, 534
Bermudez asphalt, 7
Bicycle/walking paths, in asphalt, 742
Bins, for virgin aggregate and RAP cold-feeds, 317–318
Bitumen, 23
Bituminous surface treatment, *see* Chip seal
Blade mixing, for cold-laid pavements, 715–716
Blast Furnace Slag (BFS), 116, 128
Bleeding, or flushing, 554
Blend formula, in modern batch-plant production, 333
Blending chart, 643–644
Blisters, 633
Block copolymer, 87
Block cracking, 543
Bonding roof deck and pavement, 752
Breakdown rolling, 436–439, 649, 662

Bridge-deck paving
construction methods, 750–751
dense-graded asphalt concrete mixtures, 750
Brittle, defined, 56
Bucket-elevator method, 338–339
Bulk specific gravity, 129
of aggregates, 175–176
of the HMA mixture, 179–181
testing for, 467–468
Burlington Northern-Santa Fe Railway's double-tracking, 737
Burner flighting, of dryers, 320–321

C

CA, FA_c and FA_f ratios, 216
Calcareous aggregates, 166
Calcium chloride, 74
Calibrated pycnometer, 176
Calibration process, 344
accuracy, 318
California bearing ratio, 252–257
California Kneading Compactor, 205
Cannon-Manning vacuum viscometer, 28
Cantabro test, 226
Cape seal, 613–614
Capillary water, 271
Catch basin system, 274
Cationic emulsified asphalts (ASTM D 2397), 77
Cationic rapid-setting (CRS) emulsions, 74
Cement-mixing test, 74
Centrifuge Kerosene Equivalent (CKE) tests, 204
Chemical modification, 90
Chip seal, 12, 587, 634
construction sequence, 600–603
equipment for, 594–603
limitations, 604
longitudinal joints, 604
materials, 590–591
surface treatment design, 591–594
transverse joints, 604
Class C fly ash, 655, 662
Cleveland Open Cup (COC) flash point test, 34, 65, 81
Close-proximity (CPX) noise trailer, 747
Coal-tar products, 23
Coarse aggregate angularity (CAA), 466
Coarse-graded aggregate structures, 135
Coarse graded mix, 215
Cohesiometer, 205
test, 204
Cohesion, of mix, 164
Cold In-Place Recycling (CIPR) process
application, 655
compaction of layers, 661–663
criteria for suitability, 656
curing and aeration, 663
equipment and methods, 658–660
inspection, 664–665
mix design, 656–657
placement of materials, 661
wearing course, 664
Cold milling, a pavement
application, 637
equipment for, 638–640
inspection, 641
micromilling *versus* conventional milling, 638
specifications, 640–641
Cold mix asphalt preparation
construction methods, 712–714
description, 705–706
methods of preparing mixes, 714–723
mix composition, 706
proportioning materials, 710–711
suitability for pavement construction, 706
type and grade of asphalt in, 706–708
types, 708–710
Cold-mix recycling
central plant (CP) cold recycling, 652–653
defined, 652
placement of mix, 654
stationary facilities, 653–654
Cold-plant asphalt mixtures, 573
Cold-side rolling, 442
Colored asphalt, 764
Combination plant, 342
Compacted recycled surface, 646
Compaction, 646
acceptance for, 494–495
of a CIPR mix, 661–663

control methods, 486–489
in cool weather, 424
equipments, 426–433
factors affecting, 419–423
general operational notes, 433
influences on, 425
mechanics, 418–419
need for, 417
of reclaimed mixes using foamed asphalt, 673
rolling procedures, 434–442
terms and definitions, 416–417
thickness of the lift, 435
troubleshooting, 443–444
Compactive force, of a pneumatic-tire roller, 429
Complex shear modulus, 52, 65
Composite-aggregate gradation, 136
Compression-based equipments, 118
Concrete linings, for hydraulic applications, 728–732
Condition survey, of pavements, 524
Conical piles, 652
Consistency, of an asphalt binder, 26–27
Construction control testing, 171
Contact pressure, of a pneumatic-tire roller, 429
Contamination prevention, during process, 315–316
Continuous weigh pod for baghouse dust or filler, on drum plant, 328
Control systems, of a plant
aggregate and RAP transfer conveyors, 318–319
aggregate dryer, 319–322
aggregate stockpiling, 315–317
dust collection equipment, 322–325
dust-return equipment, 325–327
for fiber additives, 329
finished product storage silos and load-out equipment, 329–331
lime additive bulk storage and feed silos, 328
liquid asphalt storage tanks, 313–315
mineral filler additive storage and feed silos, 327–328
virgin aggregate and RAP cold-feed bins, 317–318
Conveyor belt sampling techniques, 455–458
Conveyors, for aggregate and RAP transfer, 318–319
CoreLok® procedure, 179–180
CoreLok® vacuum-sealing device, 181, 226
Core sampling, 460
Corrugations and shoving, 547–548
Counterflow drum-mixer flow, 341
Cracking and seating, on pavements, 687–688
on JCPC pavements, 689
Crack sealing/filling, 626–627
filling procedures, 585
materials, 583
purpose, 582–583
sealing procedures, 583–584
Creep stiffness, 54, 56
Creep testing, 232–234
Cross-arm viscometers, *see* Zeitfuchs cross-arm viscometer
Crude oil chemical composition, 23–24
Crude oil distillation process, 23
Crumb rubber modification, 89–90
Crumb-rubber modified-asphalt binder, 749
Crushed sand, 115
Crushed stone, 114–115, 123
"Crusher-run" aggregate, 115
Crushing, process of, 114, 117–118
CSX Transportation rail crossing, in northern Ohio, 738
Cutback asphalts, 9, 71–72
specifications for, 81–82
tests for, 78–81
Cyclone and baghouse, on drum-mix plant, 323

D

Decibel or dB, defined, 746
Deep patching, 573–574
Degradation, 119
Deleterious substances, 130–132
Delivery, of HMA
material surge at paving site, 370–374
at paving site, 370
recording of, 374–375
using haul trucks, 366–370
visual inspection of, 375

Demulsibility test, 74
Dense-graded aggregate mixtures, 709
Dense-graded paving mixes, 162
Density tests, 451
Density-voids calculations, 173
Direct tension test, 58
Disintegration, of pavements, 550–551
Distillation test, 76
Distortions, in the pavement layer, 547–550
Drainage, of the pavement structure, 629
  design, 270–271
  geotextiles as alternative designs, 278–279
  rationale for, 270
  subsurface
    drainage related to frost action, 276–278
    drainage schemes, 275–276
    filter material and drain rock, 275
    surface
    design for large paved areas, 273–274
    design for roadways, 271–273
Drainage ditches, 272
Drain rock, 275
Drum-mix production process, 311–312
  aggregate gradation control, 342–345
  asphalt content control, 345–347
  development of, 340–342
  mixing/coating, 347–348
  production problem-solving guide, 350–352
  recycled mix production, 348–349
Dryers, 319–322
Dry-mix cycle, in batch production process, 311
Dry sieving, 121
DSR Repeated Creep Test, 93
Ductile, defined, 56
Ductility, 36–38
Durability, of an asphalt pavement, 166
Dust collection equipment, 322–325
Dust palliatives, 589
Dust-return equipment, 325–327
Dynaflect, 534
Dynamic modulus test, 231
Dynamic shear rheometer (DSR), 49–53, 211
Dynatest, 266

E

Edge cracks, 543–545
Effective asphalt content (P_{be}), 173
  of a paving mixture, 183–184
Effective specific gravity (G_{se}), 129
  of aggregate, 178–179
Elastic modification, *see* Elastomers
Elastic Recovery test, 89, 93
Elastomers, 87
Electro-negatively charged asphalt droplets, 9
Electro-positively charged asphalt droplets, 9
Elongation of geotextile at break, determination, 630
Emulsified-asphalt, 9, 69–71, 667
  content, 710
  specifications for, 77–78
  tests, 72–77
  use, 72
Emulsion-based process, 766–767
End-result specifications, defined, 513
Environmental applications, of asphalt
  fish hatcheries, 755
  landfill caps, 756
  water reservoir liners, 755–756
Environmental control system, 59
Equivalent Single Axle Loads (ESALs), 190
Ethylene vinyl acetate (EVA), 89
Expanded Shale, Clay, and Slate (ESCS), 116
Extenders, 90
Extraction, of aggregates, 117
Extrusive rocks, 113
Exudation pressure test, 259–260

F

F. C. Field of the Asphalt Institute, 3
Failure strain, 58
Failure stress, 58
Falling weight deflectometer (FWD), 534

Fatigue cracking, 165, 615
factor, 66–67
Fatigue resistance, 164–165
Fatty amidoamines, 91
Feed-bin calibration process, 317
Feed bins, for virgin aggregate, 317
Feeders, 344
Fiber additive equipment, 329
Fine aggregate angularity (FAA), 466
Fine-graded aggregates, 135
Fine graded mix, 215
Fines-return system, on drum-mix plant, 325–327
Finished product storage silos and load-out equipment, 329–331
Finish rolling, 440
Fire point, 34
Flash point, 27, 34
Flexural fatigue test, 234–236
Float Test, 70, 77
Foamed asphalt, 667, 766
Foaming mineral additives, 766
Fog seals, 588
Foliation, 113
Force Ductility test, 89, 94
Fractured-faces specifications, 465–466
Fractured slab technique
construction procedure, 689–692
crack/break and seating of pavements, 687–688
Free-fall compensation value, 336
Free-movement plane construction, 752
Freeze-thaw resistance, of an aggregate, 130
Frost heaves and drainage system, 276
Full-depth asphalt pavement, 15
Full-depth patching, 573–576
Full-depth Reclamation (FDR)
asphalt stabilization, 667–669
chemical stabilization, 666
construction procedure, 669–672
inspection, 674–675
shaping and compaction procedures, 672–674
Functional conditions, of a pavement
pavement distress, 529–531
ride quality, 531–532
surface friction, 532–534

G

Gap-graded aggregates, 135
Gas-free distilled water, 175–176, 178
Gate openings, in production process, 317
Gear-type pumps, 594
Geographic information systems (GIS), 525
Georgia Loaded Wheel Tester (GLWT), 237
Geotextiles
as interlayers for HMA pavements, 629–633
in subsurface drainage systems, 278–280
Gilsonite deposit, 7, 91
Glasphalt, 116
Glass-like structure rocks, 113
Gneisses, 113
Grab tensile strength, of geotextile, 630
Gradation blending calculations, 139–144
Gravel, 113–114
Gravities, for aggregates, 128–130
Griptester, 533

H

Hairline cracks, 582
Hamburg Wheel-Tracking Device (HWTD), 237
Handling and stockpiling, of aggregates, 118–119
Harsh mixtures, 167
High-float medium setting (HFMS) emulsions, 653
High-tensile strains, 165
"Highway class" vibratory rollers, 433
HMA mixture sampling, 458–462
Hot-air blasting procedure, 583
Hot In-place Recycling (HIPR), 622
categories, 642
construction process, 644–649
inspection, 649
material evaluation, 643–644
pavement assessment, 642
Hot mix asphalt (HMA), 4, *see also specific topics*
adoption of Superpave mix design system, 163

aggregates for, *see* Aggregates, for hot mix asphalt (HMA) mixture
classification, 161–162
defined, 161
evolution of, 162–163
joint construction, *see* Joint construction, of HMA
Hot-side rolling, 441–442
Hubbard, Prevost, 3
Hubbard-Field Method, 162
Hubbard-Field test, 4
Hveem, Francis, 4
Hveem method, of asphalt refining, 4
Hveem method, of mix design, 163
description, 204–205
design criteria, 205–209
Hveem Stabilometer, 163, 205, 260
Hydrated lime, 91, 655
Hydraulic application, of asphalt
asphalt seals, 732–733
construction considerations, 730–733
impermeable surface lining mixes, 727–728, 730–732
mix design requirements, 727–730
Performance Grade (PG) of asphalt, 728
permeable surface lining mixes, 728–730, 732
porous drainage layers, 732
sub-liner drainage layers, 730–732
various uses, 724–727
Hydrocarbon modifiers, 91
Hydroplaning, 166

I

Ideal velocity of flow, in a ditch, 273
Igneous rocks, 113
Independent assurance, 447
Industrial floors, using asphalt, 751
Inertial profilometers, 497–498
In-place pavement sampling, 460
Intelligent Compaction (IC), 433
Interlayer techniques
chip seals, 634
construction procedure, 635
functions of interlayers, 629
inspection procedure, 636
paving membranes, 633
stress-absorbing membrane interlayer (SAMI), 634–635
strip interlayers, 633–634
use of geotextiles, 629–633
Interlocks, 123
Intermediate rolling, 439
Intrusive rocks, 113

J

JILS, 266
Job-mix control testing, 171
Job-mix formula, 171
quality-control and acceptance of, 449–450
verification, 476–477
Joint construction, of HMA
longitudinal joints, 401–403
notched-wedge joints, 403
during paving start-up procedures, 399–401
traverse or construction joints, 398–399

K

KENTRACK, 737
Kinematic viscosity, 30
test, 78
Knockout box, on drum-mixer plant, 323
KUAB, 266

L

Laboratory test methods
California bearing ratio, 252–257
resilient modulus (M_r), 261–263
resistance value (R-value), 257–261
Leaching pads
construction, 753–754
design, 753
materials, 753
uses, 753
Leveling courses, 432, 626
Leveling wedges, 626
Lifecycle cost analysis (LCCA), of pavements, 522
Light steel-wheel rollers, 731
Lime additive bulk storage and feed silos, 328
Linear Variable Differential Transformers (LVDTs), 261

Linear viscoelastic (LVE) range, of material, 52
Liquid antistripping additives, 91
Liquid asphalt storage tanks, 313–315
Liquid limit (LL), 131, 250
Load-penetration test, 255–256
Longitudinal cracks, 545
Longitudinal joints, 441–442
Longitudinal streaking, 555
Los Angeles Abrasion test, 127–128, 187
Lottman method, 227
Low density polyethylene identified (LDPE), 89
Low-Energy Asphalt (LEA), 766
Low-temperature cracking, 165

M

Marble, 113
Marshall, Bruce, 4
Marshall method, of asphalt refining, 4
Marshall method, of mix designing, 162
  description, 198–201
  design criteria, 201–203
Mechanical extraction tools, 117
Mechanistic Empirical Pavement Design Guide (MEPDG), for highways, 694
Medium-curing (MC) cutback asphalts, 71
Metamorphic rocks, 113
Method specifications, defined, 513
Micro-Deval test, 127
Micromilling process, 638
Micro PAVER pavement management system, 536
Microsurfacing, 12, 587
  application procedure, 613
  equipments for, 610–612
  joints, 613
  materials, 610
  surface preparation, 613
  weather limitations, 613
Mineral additives, 766
Mineral aggregates, 187
Mineral filler additive storage and feed silos, 327–328
Mix behavior, of HMA
  air-voids, 168
  asphalt content, 169–170
  density, 167–168
  voids filled with asphalt, 169
  voids in mineral aggregates, 168–169
Mix deficiencies and causes, in batch production process
  gradation shift/aggregates, 353
  gradation shift/coarser on –200 mesh (75 micron) sieve, 353
  gradation shift/finer on –200 mesh (75 micron) sieve, 351
  high AC content, 354
  high voids, 351
  inadequate coating, 355
  low AC content, 354
  low air-voids, 354
  temperature fluctuations, 355
Mix deficiencies and causes, in drum-mix production process
  gradation shift/aggregates, 350
  gradation shift/coarser on –200 mesh (75 micron) sieve, 351
  gradation shift/finer on –200 mesh (75 micron) sieve, 351
  high AC content, 351–352
  high voids, 351
  inadequate coating, 352
  low AC content, 352
  low air-voids, 351
  temperature fluctuations, 352
Mix density, 167–168
Mix design
  for bicycle/walking paths, desired properties for, 742–743
  Cold In-Place Recycling (CIPR) process, desired properties for, 656–657
  durability, desired properties for, 166
  fatigue resistance, desired properties for, 164 –165
  formula for, 178
  low temperature cracking, desired properties for, 165
  moisture resistance, desired properties for, 165–166
  procedures for the design of open-graded friction courses, 224–227
  race tracks, desired properties for, 758–759

resistance to permanent deformation, desired properties for, 164
skid resistance, desired properties for, 166
workability, desired properties for, 166–167
Mix Design Formula (MDF), 344
Mixed-polymer modification, 90
Mix pickup, 443
Mix selection
dense graded mixes, 243–244
determination of mix types, 244–245
pavement layers and traffic levels, 242–243
Mixture compactability, 489–490
Moisture damages, in HMA pavements, 165–166
Moisture susceptibility test, 196
Molten materials (magma), 113
MS-17 manual, 541, 622
Multihead Breaker (MHB), 697–698
Multiple-stress creep-recovery (MSCR) test, 93, 96
Multi-unit train, 660

N

National Center for Asphalt Technology (NCAT), 747
National Institute for Certification of Engineering Technicians (NICET), 449
National Voluntary Laboratory Accreditation Program (NVLAP), 449
Natural asphalts, 7
Negative weigh pod system, 326
Network-level analysis, of pavements, 526
Newtonian fluids, 44
Noise reduction, using asphalts
nature of noise, 746–747
noise characteristics of HMA pavements, 747–749
Nondestructive testing (NDT), 529
Non-ionic emulsions, 70
Nonwoven geotextile specifications, for pavements, 630

O

"Ointment" or "cigar" tube test, 92
Open-graded cold mixes, 708
Open-Graded Friction Course (OGFC), 11, 329, 748–749
description and usage, 223–224
mix design characteristics and procedures, 224–228
Open-graded mixes, 135, 162
Organic wax-like additives, 766
Overlay selection, for pavements
alternatives for, 623
construction feasibility, 622
pavement condition, 622
performance, 624–625
Oxidants, 90
Oxidative hardening, 46

P

Parallel-flow drum-mixer flow, 341
Parallel-flow dryers, 340
Particle charge test, 75
Patcher truck, 576
Patching
full-depth (deep) patching, 573–576
materials, 573
spray injection patching, 580–581
surface patches, 576–580
Pat Test, 162
Paved shoulders, 272
Pavement condition index, 538
Pavement deflection testing, 534
Pavement deterioration, 542
Pavement distress surveys
approaches, 539–541
types of distress, 541–557
Pavement maintenance, asphalt in
asphalt surface treatment, 587–614
corrective maintenance, 571–572
crack sealing/filling, 582–585
emergency maintenance, 572
guidance maintenance procedures, 616
patching, 573–581
preventive maintenance, 571
thin overlays, 615
Pavement management
analysis module, 524–525
components, 523–525

concept, 521–523
database, 524
evaluation of functional condition of a pavement, 529–533
network-level analysis, 526
project-level analysis, 526
reporting tools, 525
role in pavement preservation, 527–528
strategic-level analysis, 526
structural characteristics and evaluation, 534–535
use of information, 536–538
Pavement performance models, 525
Pavement preservation program
development of a program, 559
guidelines for treatments, 562
maintenance and rehabilitation treatments, 563
need estimation, 559
prioritizing project needs, 563–565
selection of appropriate treatments, 560–561
setting goals, 559
success of, 565–566
use of pavement management, 558
Pavement rehabilitation
CIPR process, 655–665
cold milling, 637–641
cold-mix recycling, 652–654
considerations in overlay selection, 621–625
crack filling/sealing, 626–627
drainage problems, 629
FDR process, 666–675
HIPR, 642–649
interlayer techniques, 629–636
leveling of courses, 626
patching techniques before placing overlay, 626
tack coat application, 627
widening of pavements, 628–629
Pavements, of asphalt
basic concepts, 13–14
base and subbase layers, 15
stage construction, 16–17
surface course, 14–15
thickness, 15–16
using cold-laid asphalt mixture, 706
Pavement smoothness, 492, 496
Paving equipment
asphalt paving machine, 377–379
automated screed controls, 388–392
free-floating screed, 392–396
fumes control system, 396
screed observation system, 396–397
screeds, 381–388
types of tractors, 379–381
Paving fundamentals, *see also* Pavement rehabilitation; Paving equipment
asphalt distributor, 365
delivery of HMA, *see* Delivery, of HMA
foreman's/inspector's check sheet, 411–412
hand-spreading operations, 404
horizontal and vertical grade control, 362–363
preparation of existing pavement for overlay, 362
pre-paving conference, 359
prime coats, 363–364
supplemental operations and appurtenances, 404–410
surface preparation and protection, 360–362
tack coats, 364–365
Paving mixture data, 174
Paving mixtures, for cold-laid pavements
aeration/spreading/compaction, 720–722
blade mixing, 715–716
rollers suitable for, 723
rotary mixing, 716–717
stationary mixing facilities, 719
travel-plant mixing, 717–719
Pay reduction factors, for HMA production, 509–512
Pen asphalt binder, 40
Penetration-Graded Specification, 40, 42
Penetration tests, 84–85
Penetrometer, 32–33
Percent Within Limits (PWL), 506
Performance-based specifications, of HMA, 513–515
defined, 514
warranties, 516–517

Performance Graded (PG) asphalt binders, 198
Performance specifications, defined, 513–514
Permanent deformation, 164
Petroleum asphalt, 7
  flow chart, 25
  properties or characteristics of, 26–27
  refining process, 23–26
Petroleum pitches, 23
PG asphalt binder specification
  advantages, 63–64
  assumptions, 65
  performance measures, 65–68
PG asphalt binder tests
  aging procedures, 60–63
  bending beam rheometer, 53–56
  direct tension tester, 56–60
  dynamic shear rheometer (DSR), 49–53
  rotational viscometer, 47–49
PG 58–28 binder, 743
PG 64–22 binder, 743
PG 64–28 binder, 743
Physical hardening, 47
Pit or bank-run materials, 113–114
Placement quality-control
  compaction control methods, 486–489
  mixture compactability, 489–490
  pavement smoothness, 492
  temperature, 483–485
  thickness and spread rates, 490–492
Plant sampling, 458–459
Plasticity index (PI), 131, 250
Plastic modification, *see* Plastomers
Plastomers, 89
Plate sampling, 462
Pneumatic hammer, 579
Pneumatic rollers, 632–633, 646, 751
Pneumatic-tire rollers, 427–429, 602
Polished aggregates, 554
Polyamines, 91
Polyethylene, 86
Polyethylene tubing, 696
Polymer modified asphalts (PMAs), 11, 86
  binder, 164
Polyolefin polymers, 87, 89
Polyphosphoric acid (PPA), 90
Pore structure, of an aggregate, 128
Porosity, of aggregates, 128
Porous asphalt pavement
  construction, 763
  design principles, 761–763
  maintenance, 763
Portable silos, 330
Portland cement, 655, 662
Portland cement concrete (PCC) pavement, 545
Potholes, 550–551
Power gradation curve, 136–139
Power sweepers or brooms, 587, 600
Pressure Aging Vessel (PAV), 60
Production processes
  batch facilities, *see* Batch production process
  drum-mix facilities, *see* Drum-mix production process
Profilographs, 497
Project-level analysis, of pavements, 526
Proofrolling, 626
Propane deasphalting (PDA), 26
Pugmill mixer, 648
Pulverization, of the existing pavement, 669–672
Pycnometer, 39

Q

Quality assurance, 447
Quality control, of plant production
  job mix formula, 476–477
  mixture control, 477–481
  plant adjustments, 481–482
Quality-control and acceptance, of HMA
  definitions, 447–449
  job-mix formula (JMF), 449–450
  "performance-based" specifications, 513–515
  selection of sampling methods and frequency, 470–471
  selection of testing methods, 471–472
  testing criteria, 448
  test strip, 474–475
  written plan for, 472–474
Quarried aggregates, 114–115

Quarry stone, 117
Quick Set Slurry Seal systems, 72
Quick-setting (QS) asphalt emulsion, 606

R

Racetracks, with HMA
  aggregate in, 758
  asphalt binder in, 758
  characteristics of tracks, 757
  construction practices, 759–760
  drainage, 758
  materials required, 758–759
  tack coat application, 760
  test tracks, 757
Railway track beds, HMA in
  benefits and applications in underlayment, 735–736
  installation, 737–739
  prevailing design practices, 736–737
Random sampling techniques, 453–454
Rapid-curing (RC) cutback asphalts, 71
Rapid-setting (RS) emulsions tests, 74
Raveling, 551
Reclaimed (or recycled) asphalt pavement (RAP), 91, 637
  mix design, 213–214
    materials evaluation, 210–213
  processing, 147–148
  sampling and testing, 149–151
  stockpiling, 148–149
Recycled glass, 116
Reference density specifications, 503
Reflection cracking, 545, 629, 679–681
  on asphalt pavements, 625
  fractured slab techniques for, 687–692
  rubblization process, 693–700
  saw-and-seal application, 682–686
Reflection cracks, 547
Rejuvenators, 589
Remaining service life (RSL), 537
Repaving, in HIPR process, 646–647
Representative sampling, 451–453
Residue tests, for emulsified asphalt grades, 80–81
Resilient modulus (Mr), 261–263
  test, 231–232, 269
Resistance value (R-value), 257–261
Resonant Pavement Breaker (RPB), 696–697
Response Type Road Roughness Measuring (RTRRMS) systems, 497
Ride quality, 496
Ring-and-ball softening point test, 83–84
Rock quarry excavation, 114
Rocks, 111–113
Roller marks, 444
Rollers, 599
Rolling edges, 442
Rolling thin film oven (RTFO), 211
Rolling Thin Film Oven Test (RTFOT), 35–36, 60
Roof deck parking
  bonding roof deck and pavement, 752
  free-movement plane construction, 752
Roofings, of asphalt
  history, 744
  types of, 744–745
ROSE unit asphaltenes, 91
Rotary mixing, for cold-laid pavements, 716–717
Rotational viscometer, 47–49
Rotavapor procedure, 211
Rounded boulders and pebbles, 114
Rubberized asphalt adhesive, 633
Rubber-tire rollers, *see* Pneumatic-tire rollers
Rubblization
  construction, 694–700
  design considerations, 693–694
  project selection and overview, 693
  specification criteria and inspection, 700
Running tracks, in asphalt, 740
Rutting, 536, 548
R-value test (ASTM D 2844), 258

S

SAAB Friction Tester, 533
Sampling, of hot mix asphalt
  aggregate method, 454–458
  asphalt binder, 463
  mixture, 458–462
  random, 453–454
  representative, 451–453
Sand, 113–114
Sandblasting, 583

Sand-emulsion plant mixes, 710
Sand-equivalent test, 131
Sand seal, 614
Sandy soil mixtures, 114
Saturated surface-dry (SSD) mass, 180
Saw-and-seal, in prevention of reflection cracks
  construction, 683–686
  design considerations, 683
Saybolt Furol viscosity test, 72–73
Schists, 113
Scratch courses, 626
Screening, of aggregates, 118
Screenless mixing, 333
Scrubber, on drum-mix plant, 324
Seal rollers, *see* Pneumatic-tire rollers
Sedimentary deposits, features of, 111
Sedimentary rocks, 111
Segregation, 119
Self-propelled pneumatic-tire roller, 427, 599
Self-propelled spreader, 597
Settlement or grade depressions, 548
Shear modulus test, 230–231
Shear Rate Changes, of asphalt binder, 45
Sideways-Force Coefficient Routine Investigation Machine (SCRIM), 533
Sieve test, 75–76
Silt fraction, 113
Single-unit train, 659
Skid hazards, 551–554
Skid resistance, 166
Slag, 116
Slate, 113
Slippage cracks, 547
Slotted or z-wire screens, 335
Slow-curing (SC) cutback asphalts, 71
Slurry seal, 12, 587
  construction process, 607–609
  materials, 605–606
  mix design, 606
Slurry seal machine, 607
Soil strength/stiffness, testing of
  field test procedures
    using Dynamic Cone Penetrometer (DCP), 263–266
    using falling weight deflectometer (FWD), 266–268
  laboratory test methods
    California bearing ratio, 252–257
    resilient modulus (Mr), 261–263
    resistance value (R-value), 257–261
  routine tests, 253
  strength correlations, 269
Soil-subgrade classification systems
  AASHTO system, 249–250
  rationale for, 249
  USCS system, 249–250
Solubility test, 38, 92
Solvent deasphalting (SDA), 26
Specific gravity, of an asphalt binder, 39
SP-2 manual, 188–189, 192
Spray-applied seal, 12, 587
Sprayed asphalt sealers, 732
Spray-injection patching, 580
Stabilometer, 204
Standard paving machine, 648
Static steel-wheel rollers, 438
Stationary mixing, for cold-laid pavements, 719
Steam release, in bucket-elevator method, 339
Steel loading strips, 197
Steel-wheel rollers, 426–427
  bridge, 599
Stockpile sampling techniques, 454–455
Stone matrix asphalt (SMA) mixtures, 11, 162, 215, 329, 748
  draindown test, 221–222
  material selection, 218–219
  mix design, 217–218
  selection of desired gradation, 219–221
Stone-on-stone contact, determination of, 220
Storage facilities, in plant automation
  finished product, 329–331
  lime additive bulk, 328
  liquid asphalt, 313–315
  mineral filler additive, 327–328
Storage silos, 329
Storage stability and settlement tests, 73–74
Straightedge measurements, 497
Strategic Highway Research Program (SHRP), 4, 163
Strategic-level analysis, of pavements, 526

Stress-absorbing membrane interlayer (SAMI), 634–635
Strip interlayers, 633–634
Stripping, 165
Styrene-butadiene copolymers, 87
Styrene-butadiene (SB), 87
Styrene-butadiene-styrene (SBS), 87
Styrenic polymers, 87
Subsurface drainage
  drainage related to frost action, 276–278
  drainage schemes, 275–276
  filter material and drain rock, 275
Subsurface, 274
Subsurface water, 274–276
Sulfate soundness test, 130
Superpave Gyratory Compactive effort, 191
Superpave Gyratory Compactor (SGC), 189, 237
Superpave (SUPerior PERforming Asphalt PAVEments) system
  aggregate structure, design of, 188–194
  design asphalt binder content, 194
  design to adjust properties, 194–196
  material selection, 186–188
  moisture sensitivity, 196–197
Superpave system, 8
Surface drainage, design
  for large paved areas, 273–274
  for roadways, 271–273
Surface friction, 532
Surface patches, 579
Surface recycling, in HIPR process, 644–646
Surface runoff, 271
Surface treatments, with asphalt, 12
SW-2 computer program, 140
Synthetic and lightweight aggregates, 115–116

T

Tachometer, 595, 599
Tack coat application, in hydraulic construction, 731
Tag Open Cup Flash Point test, 78, 81
Temperature control, in HMA operations, 468–469, 483
Temperature-volume relationship
  density and specific gravity, 102–103
  specific gravity calculations, 104
  tank measurements, 104–105
Tennis court, in asphalt, 741–742
Testing methods, of HMA, 170–171
  aggregate gradation, 464–465
  air-voids, 468
  asphalt content, 466–467
  bulk specific gravity of mixtures, 467–468
  creep test, 232–234
  empirical tests, 236
  flexural fatigue test, 234–236
  fractured faces and aggregate angularity, 465–466
  goal, 464
  modulus test, 230–232
  temperature, 468–469
  theoretical specific gravity of mixtures, 467
  wheel-tracking tests, 237–241
Tests, for asphalt cement
  aging, 34–36
  ductility, 36–38
  flash point, 34
  penetration, 32–34
  solubility, 38
  specific gravity, 39
  viscosity, 28–32
Test strip, 434
  for quality control, 474–475
Thermal cracking, 67–68
Thermoplastics, 86
Thermosets, 87
Thicker lifts, 432
Thickness design, for pavements
  acceptance level, 496
  airports, 291–293
  design principles, 284–287
  empirical design methods, 297
  heavy wheel loads, 293–295
  highways, roadways and streets, 289–291
  input variables, 287–289
  manuals and software, 302–305
  mechanistic-empirical design methods, 297–298
  overlay design, 295–296
  Perpetual Pavement methods, 298–301

planned stage construction, 295
quality-control testing for, 490–491
Thin Film Oven Test (TFOT), 35
Thin overlays, 615
Toughness, of aggregates, 126–128
Toughness and Tenacity test, 89, 96
Trackbed designs, with HMA, 735–739
Transverse cracks, 545
Transverse joints, 440–441
Transverse streaking, 555
Travel-plant mixing, for cold-laid pavements, 717–719
Trinidad Lake Asphalt (TLA), 7, 91
Truck-mounted mechanical spreaders, 597
Truck sampling, 459
Tungsten carbide milling teeth, 638–639
Twin-shaft pugmill mixer, 337
Two-unit train, 659–660

U

Unitized dryer/mixer, 340, 342
Upheaval or swell, 548–550
Utah Department of Transportation (UDOT), 522

V

Vacuum distillation, 23
Variable-speed belt feeds, 317
Vibratory rollers, 429–431
Vibratory steel-wheel rollers, 731
Viscometers, 28–32
Viscosity test, 42
Voids, significance of, 126
Voids filled with asphalt (VFA), 169, 172
adjustments, for changing properties, 196
Voids in the mineral aggregate (VMA), 168–169, 172
adjustments, for changing properties, 194
in compacted paving mixture, 184
Volatilization, 46
Volumetric calculations
acceptance of, 494
analysis of paving mixtures
air-voids, 184–185
apparent specific gravity, 175
asphalt absorption, 181–183
bulk specific gravity, 175, 179–181
effective specific gravity, 178–179
gravity for the aggregate combination, 176
maximum specific gravity of the HMA mixture, 176–178
percent of voids filled with asphalt (VFA), 185
percent of voids in mineral aggregates, 184
definitions, 172–173

W

Warm mix asphalt pavements
benefits, 765
technology, 765–767
Warranties, 516–517
Washboarding, 547–548
WASHO Road Test, 535
Water-displacement procedure (AASHTO T 166 or ASTM D 2726), 181
Water-spray systems, 439
Wearing course, 664
Weathering, 551
Weathering resistance, 130
Weigh-hopper method, 338–339
Well-graded aggregates, 135
Wet-mix cycle, in batch production process, 311
Wet washers, on drum-mixer plant, 322
Widening, of pavements, 628–629
Windrow sampling, 460
Workability, of paving mixture, 166–167

X

Xylene, 79

Z

Zeitfuchs cross-arm viscometer, 30
Ziggurats, 3