Adaptability · Respond to the change

Apply the change card, identify what changes and what stays, and revise the record.

Evidence and feedback: Use the change-response key below; retain the earlier version and do not alter unrelated facts.

Creativity and innovation · Make understanding easier

Create a labelled SVG, annotated plan, short audio explanation or captioned storyboard that makes the issue easier to understand. Test it with a reader/listener and improve one useful detail.

Evidence and feedback: The visual/media has accurate labels, source credits and a stated purpose. Inspect generated diagrams/media; do not invent technical settings. Keep a transcript/captions when producing audio/video.

Change card · Use after the first attempt

A corrected drawing changes width to 3.6 m before placement; the mass allocation has not been revised.

Verified case key

Area 280 m²; actual rate 33,600/280 = 120 kg/m², or 100% of specified. HI 101.300; measured EL 99.580; fill 70 mm at that point. Application rate alone does not establish density, smoothness, uniform thickness or acceptance.

Change-response key

New area 288 m². The same 33.6 t would give 116.67 kg/m², about 97.22% of 120. Confirm the authorized quantity/layout change before treating it as the current plan.

Individual evidence record

Keep the brief, calculation, saved work, review findings and revision. Record each person’s actual contribution and support. Use Not observed, Not yet demonstrated, Demonstrated with support, or Demonstrated independently for the stated action; these are local feedback descriptions.

For AI/media work, a transcript, script or storyboard is distinct from a generated audio/video file. Name what was actually produced and inspected. Do not upload private records or community-held material without the relevant authority.