Working reference and evidence record

Words used in this book

Term	Meaning in these lessons
Aggregate	Mineral material such as sand, gravel or crushed stone
Asphalt binder / asphalt cement	Binding material in an asphalt mixture; distinct from Portland cement
Batch plant	Production arrangement that makes identifiable batches
Drum-mix plant	Production arrangement using a continuous material/mixing process; layouts vary
RAP	Reclaimed asphalt pavement material considered for an approved reuse pathway
Hot-in-place recycling	Specialist process treating existing asphalt pavement on the road
Screed	Paver component that contributes to forming the placed mat
Compaction	Densification process performed according to the applicable approved procedure
Milling	Removal or profiling of existing material using suitable equipment
Chainage	Position measured along a defined project line
Plan / profile / cross-section	Top view / elevation along a line / cut across a route
Crown	Raised transverse road form that can direct surface water toward sides
Superelevation	Cross-slope arrangement associated with a curve; design is project-specific
Runoff	Water moving from a surface
Specification	Documented requirements; applicability depends on its legal/contractual context
Special provision	Project/contract-specific provision that may modify or add requirements
Revision	Identified version of a document
Functional comparison	Comparison based on an equivalent required service, period and conditions
Life-cycle boundary	Stages included and excluded in an environmental assessment
Percentage point	Difference between two percentages expressed on the same basis
EPS in the 2006 specifications	End Product Specification, explicitly defined in clause 502.03.01; identify the edition and context before applying the term
EPS geofoam	Expanded-polystyrene material for an engineered geotechnical application; an abbreviation's meaning still depends on context

Record evidence without overstating it

For each selected activity, record: activity ID; date; task and document version; what you did; support used; result; check; feedback; revision; and next practice. Mark the observed skill. A group product needs an individual contribution record. An accurate calculation needs units and assumptions. A digital claim needs actual tool use. A future application is a plan until it has been observed.

Activity	Evidence kept	Support and feedback	Next practice
_____	_____	_____	_____
_____	_____	_____	_____
_____	_____	_____	_____

Sources and continuing questions

The research register provides public titles, issuers, dates, URLs, retained short excerpts and retrieval hashes. It distinguishes dated factual evidence from invented classroom inputs and records questions that need current local or technical confirmation. Use the register to check a claim, then keep the question and the evidence together. A link or a confident statement alone is not the complete answer.

Supplied technical document

British Columbia Ministry of Transportation, Construction and Maintenance Branch. *2006 Design Build Standard Specifications for Highway Construction*, adopted 20 February 2006. Section 502.03.01, PDF 297 / printed 1 of 22, defines End Product Specification (EPS). The supplied historical document is distinct from the current public specifications page below; its presence does not establish current contract applicability.

Public reference list

- Province of British Columbia / WorkBC. WorkBC: Construction industry profile. 2024 observed data; 2025–2035 forecast. Retrieved 29 October 2026.
- IUOE Local 115 Training Association. Asphalt Paving Laydown Technician. Retrieved 29 October 2026; course dates listed TBA.
- B.C. Laws. Occupational Health and Safety Regulation, sections 3.22–3.25. Consolidated regulation retrieved 29 October 2026.
- Province of British Columbia. Standard Specifications for Highway Construction. Page updated 1 April 2026; 2025 edition adopted 1 February 2025. Retrieved 29 October 2026.
- B.C. project website. Kicking Horse Canyon Phase 4: Project Overview. Project completed 31 July 2024; retrieved 29 October 2026.
- B.C. project website. Kicking Horse Canyon Phase 4: Procurement/Contractor. Contract awarded 6 November 2020; completed 31 July 2024. Retrieved 29 October 2026.
- UNESCO World Heritage Centre. Via Appia. Regina Viarum. World Heritage listing 2024; retrieved 29 October 2026.
- Public Services and Procurement Canada. About the Alaska Highway. Page updated 16 December 2025. Retrieved 29 October 2026.

- U.S. Federal Highway Administration. History of the Interstate Highway System. Historical account; retrieved 29 October 2026.
- U.S. Federal Highway Administration. Recycled Concrete Aggregate: Federal Highway Administration National Review. Undated historical review page; retrieved 29 October 2026.
- Province of British Columbia. Resource roads. Page updated 5 May 2025; retrieved 29 October 2026.
- ICBC. Licence classes and types. Retrieved 29 October 2026.
- Labour Relations Board of British Columbia. Collective Agreements. Retrieved 29 October 2026.
- U.S. Environmental Protection Agency. AP-42 Section 11.1: Hot Mix Asphalt Plants. March 2004 chapter; downloaded from 2020 host path. Retrieved 29 October 2026.
- U.S. Federal Highway Administration. Porous Asphalt Pavements with Stone Reservoirs, FHWA-HIF-15-009. April 2015. Retrieved 29 October 2026.
- U.S. Federal Highway Administration. Ground Modification Methods, Reference Manual Volume I, FHWA-NHI-16-027. April 2017. Retrieved 29 October 2026.
- MMCD Association. Master Municipal Construction Documents Association. Publisher overview retrieved 29 October 2026.
- Statistics Canada. Canadian Business Counts, with employees, December 2025. Published table period December 2025; release 13 February 2026; REF_DATE 2025-07 retained. Retrieved 29 October 2026.

The curated evidence register gives the teaching use and limits; exact selected excerpts and hashes support checking. The road-industry table extract preserves the nine source rows.